

**STATE ROUTE 39  
CULVERT REHABILITATION PROJECT  
AT BROWN'S GULCH**

**INITIAL STUDY**

LA - 39 - KP 36.14 PM 22.46 EA: 4G7000



CALTRANS DISTRICT 7  
DIVISION OF ENVIRONMENTAL PLANNING  
MARCH 2003



**MITIGATED NEGATIVE DECLARATION (ND)**

Pursuant to: Division 13, Public Resources Code

**Description:**

The proposed project would be located off of State Route 39, San Gabriel Canyon Road, in the Angeles National Forest just north of the City of Azusa in Los Angeles County. The proposed project would reconstruct the culvert invert at the bottom of Brown's Gulch a canyon adjacent to State Route 39. The project has been proposed to ensure the stability of the structure which is presently compromised by scour caused by erosion and age. In order to complete this work, a temporary access ramp is necessary to transport equipment and workers to the culvert entrance.

**Determination:**

An Initial Study (IS) has been prepared by the California Department of Transportation (Caltrans). On the basis of this study, it has been determined that the proposed project would not have a significant effect on the environment for the following reasons:

- The proposed project would not impact any scenic resources or degrade the existing visual character.
- The proposed project would not impact any agricultural resources, conflict with existing zoning for agricultural use, or result in the conversion of farmland to non-agricultural uses.
- The proposed project would not conflict with or obstruct implementation of the applicable air quality plan, violate any air quality standards, effect climatic conditions, effect ambient air quality, or result in the creation of objectionable odors.
- The proposed project would not have significant impacts on biological resources, including any sensitive plant or animal species, other wildlife, and sensitive habitat communities.
- The proposed project would not impact any cultural resources, historical resources, archaeological resources, unique geologic feature, or human remains.
- The proposed project should not result in any seismic ground shaking, liquefaction, soil erosion, landslides or any other geologic impacts.
- The proposed project would not result in exposure to hazardous waste or material.
- The proposed project would not impact hydrology or water quality.
- The proposed project would not impact natural resources such as fuel, energy, or minerals.
- The proposed project would not conflict with existing land use or planning and would not induce population growth or the need for housing.
- The proposed project would not result in any social or economic impacts.
- The proposed project would not impact access to public services or recreational facilities.
- The proposed project would not impact transportation or traffic patterns, utilities or services.
- The proposed project would not result in any increase in noise.

The proposed project would result in some environmental impacts; however, measures to minimize harm are included as part of the project that would reduce impacts to a level below significance. The project would ensure the stability of the structure which would therefore enhance the safety of SR-39.

---

Ron Kosinski  
Deputy District Director, District 7  
Division of Environmental Planning  
California Department of Transportation  
District 7- Los Angeles

---

Date

**SCH #**  
**07-LA-39-PM 22.46**  
**EA: 4G7000**

**The proposed project would install an access road and rebuild the existing culvert bottom that crosses beneath State Route 39 at Brown's Gulch an intermittent stream in the Angeles National Forest, in Los Angeles County. The project has been proposed to rehabilitate the culvert invert structure in order to insure the stability of State Route 39.**

## **Initial Study (IS)**

**Submitted Pursuant to: (State) Division 13. Public Resources Code**

**THE STATE OF CALIFORNIA  
Department of Transportation**

*March 24, 2003*  
**Date of Approval**

  
**Ronald J. Kosinski**  
**Deputy District Director**  
**Division of Environmental Planning**  
**California Department of Transportation**  
**District 7 – Los Angeles**

## Table of Contents

<b>1</b>	<b>PROJECT PURPOSE AND NEED</b>	<b>4</b>
1.1	Introduction	4
1.2	Purpose	4
1.3	Need	4
<b>2</b>	<b>DESCRIPTION OF PROPOSED PROJECT</b>	<b>6</b>
2.1	No Project Alternative	6
2.2	Alternative 1	6
2.3	Alternatives Considered and Rejected	8
2.4	List of Permits/Approvals Required	8
<b>3</b>	<b>AFFECTED ENVIRONMENT</b>	<b>9</b>
3.1	Physical Environment	9
3.2	Biological Resources	9
<b>4</b>	<b>ENVIRONMENTAL EVALUATION</b>	<b>11</b>
4.1	AESTHETICS	12
4.1.1	Discussion of Environmental Evaluation Question 4.1 – Aesthetics	12
4.1.2	Measures to Minimize Harm	12
4.2	AGRICULTURE RESOURCES	13
4.2.1	Discussion of Environmental Evaluation Question 4.2 – Agricultural Resources	13
4.2.2	Measures to Minimize Harm	13
4.3	AIR QUALITY	14
4.3.1	Discussion of Environmental Evaluation Question 4.3 – Air Quality	14
4.3.2	Measures to Minimize Harm	14
4.4	BIOLOGICAL RESOURCES	16
4.4.1	Discussion of Environmental Evaluation Question 4.4 – Biological Resources	16
4.4.2	Measures to Minimize Harm	20
4.5	CULTURAL RESOURCES	24
4.5.1	Discussion of Environmental Evaluation Question 4.5 – Cultural Resources	24
4.5.2	Measures to Minimize Harm	24
4.6	GEOLOGY AND SOILS	25
4.6.1	Discussion of Environmental Evaluation Question 4.6 – Geology and Soils	25
4.6.2	Measures to Minimize Harm	26
4.7	HAZARDS AND HAZARDOUS MATERIALS	27
4.7.1	Discussion of Environmental Evaluation Question 4.7 – Hazards and Hazardous Material	28
4.7.2	Measures to Minimize Harm	28
4.8	HYDROLOGY AND WATER QUALITY	29
4.8.1	Discussion of Environmental Evaluation Question 4.8 – Hydrology and Water Quality	30
4.8.2	Measures to Minimize Harm	30

<b>4.9 LAND USE AND PLANNING</b>	<b>31</b>
4.9.1 Discussion of Environmental Evaluation Question 4.9 – Land Use Planning	31
4.9.2 Measures to Minimize Harm	31
<b>4.10 MINERAL RESOURCES</b>	<b>32</b>
4.10.1 Discussion of Environmental Evaluation Question 4.10 – Mineral Resources	32
4.10.2 Measures to Minimize Harm	32
<b>4.11 NOISE</b>	<b>33</b>
4.11.1 Discussion of Environmental Evaluation Question 4.11 – Noise	33
4.11.2 Measures to Minimize Harm	34
<b>4.12 POPULATION AND HOUSING</b>	<b>35</b>
4.12.1 Discussion of Environmental Evaluation Question 4.12 – Population and Housing	35
4.12.2 Measures to Minimize Harm	35
<b>4.13 PUBLIC SERVICES</b>	<b>36</b>
4.13.1 Discussion of Environmental Evaluation Question 4.13 – Public Services	36
4.13.2 Measures to Minimize Harm	36
<b>4.14 RECREATION</b>	<b>37</b>
4.14.1 Discussion of Environmental Evaluation Question 4.14 – Recreation	37
4.14.2 Measures to Minimize Harm	37
<b>4.15 TRANSPORTATION/TRAFFIC</b>	<b>38</b>
4.15.1 Discussion of Environmental Evaluation Question 4.15 – Transportation/Traffic	38
4.15.2 Measures to Minimize Harm	38
<b>4.16 UTILITIES AND SERVICE SYSTEMS</b>	<b>39</b>
4.16.1 Discussion of Environmental Evaluation Question 4.16 – Utility and Service Systems	39
4.16.2 Measures to Minimize Harm	40
<b>4.17 MANDATORY FINDINGS OF SIGNIFICANCE</b>	<b>41</b>
4.17.1 Discussion of Environmental Evaluation of Question 4.17 – Mandatory Findings of Significance	41
4.17.2 Measures to Minimize Harm	41
<b>5 CONSULTATION AND COORDINATION</b>	<b>42</b>
5.1 Scoping	42
5.2 Coordination with Resource Agencies	42
<b>6 LIST OF PREPARERS</b>	<b>43</b>
<b>7 LIST OF APPENDICES</b>	<b>44</b>
Appendix A Preliminary Design Layouts	45
Appendix B List of Acronyms	46
Appendix C Summary of Measures to Minimize Harm	47
Appendix D Scoping Notice	48
Appendix E Scoping Comments	49
Appendix F Mailing List	50
Appendix G Project Location Map	51
Appendix H Project Area of Impact	52



# 1 PROJECT PURPOSE AND NEED

## 1.1 Introduction

State Route 39 (SR-39), San Gabriel Canyon Road, is located in the Angeles National Forest just north of the City of Azusa in Los Angeles County. It is a two lane highway mainly used to access multi-use recreational areas within the National Forest. SR-39 runs north and south connecting State Route 2 (SR-2) and Interstate 210 (I-210).

The California Department of Transportation (The Department), Caltrans District 7, proposes to reconstruct the eroded culvert structure located on the west side of SR 39 in order to ensure its' stability. The culvert is located at the bottom of Brown's Gulch, which is an intermittent stream in the United States Angeles National Forest.

This focused Initial Study<sup>1</sup> will discuss the purpose and need of the project, project alternatives, environmental evaluation of resources in the project area, proposed measures to minimize harm, community involvement, and agency coordination. This document discusses these items pursuant to the requirements of the California Environmental Quality Act (CEQA) (Pub. Res. Code sec. 21080; Guidelines sec. 15002.).

## 1.2 Purpose

The purpose of the project is to reconstruct the culvert invert at the bottom of Brown's Gulch. The project would reconstruct the bottom of a 2.7 m diameter horseshoe shaped culvert invert approximately 180 m (600 feet) long. The invert has been scoured away due to high velocity stream flows, erosive material in the stream flow, and age.

## 1.3 Need


The existing culvert bottom has been severely eroded by years of water flow which could possibly compromise the stability of the structure. The invert of the culvert has been scoured due to high velocity stream flows, erosive material in the streambed, and age. Approximately 75% of the total length of the invert has been scoured away and ground water seeps have been filling these areas. If the bottom of this structure is reconstructed the structure and highway would remain stable. Because this culvert is located under the highway and roughly 130 feet down into Brown's Gulch, the construction of an access ramp down the hillside is required in order to complete the culvert rehabilitation.

---

<sup>1</sup> A focused Initial Study (IS) is intended to be used in instances where a project would normally qualify for a categorical exemption, but is precluded from being categorically exempt due to the "exceptions to exemptions" (14 CFR 15300.2). In a case such as this, the IS is focused on the issue which precludes the project from exemption, while still considering possible impacts associated with other resources.

Figure 1- Project Location Map

# Project Location Map State Route 39 Brown's Gulch Culvert Rehabilitation



## **2 DESCRIPTION OF PROPOSED PROJECT**

### **2.1 No Project Alternative**

The No Project Alternative would leave the culvert severely eroded. If scouring and erosion continues, the stability of the structure and the supported highway may be at risk.

### **2.2 Alternative 1**

The Preferred Alternative would rebuild the existing culvert bottom. The project would involve several steps:

1. The construction of a permanent graded access road will be necessary to repair the culvert. The access road would follow the existing drainage system path where the roadway fill slope meets the natural slope, north of the culvert and west of SR 39 (See Figure 2).
2. Reconstruct the bottom of the 2.7 m (9 feet) diameter horseshoe shaped culvert, which is approximately 180 m (600 feet) long. The reconstruction of the new bottom would occur over the existing structure See Figure 3).
3. Prior to reconstructing the culvert bottom, the eroded gullies below the existing channel invert would need to be filled with rock in order to allow for subsurface drainage (See Figure 3).
4. Modification of the culvert entrance due to the change in the bottom invert is required (See Figure 3).
5. Restoration of an eroded fill slope that abuts the highway within the project area would also be incorporated in this project.
6. Clearing and grubbing of vegetation would be required as well as grading.
7. Surrounding disposal sites would be used to obtain necessary fill for the project.


The above mentioned permanent access road will not be paved. It would be hydro-seeded with native grasses and shrubs for the purpose of erosion control.



Figure 2 – View from the edge of the roadside looking down towards the culvert invert. Proposed location of the access path.



Figure 3 – View of the culvert entrance and invert.



## **2.3 Alternatives Considered and Rejected**

### **Alternative 2**

Alternative 2 includes the same steps as Alternative 1, however, instead of grading an access road, the access road surface would be paved. This alternative would not use standard-paving machines due to the steep incline. Non-standard paving methods would lead to greater difficulty and higher costs. This, along with greater environmental impacts associated with paving the access road, make this Alternative less desirable.

### **Alternative 3**

Alternative 3 is similar to Alternative 1, but it does not provide for restoring the adjacent eroded slope. Without the restoration of the adjacent slope, the cost of the project would be reduced by \$10,000. This alternative however, would not address concerns related to erosion control within the project limits. Erosion would continue under this alternative, and possibly further compromise the stability of the slope. The additional benefit for the minimal cost of erosion control attributed by the restoration of the adjacent slope make this Alternative less cost effective.

### **Alternative 4**

Alternative 4 is similar to Alternative 1, but instead of putting concrete in the deep crevice areas, large boulders (1ft in diameter) would be placed in them with a layer of permeable material such as gravel placed over them. The invert (culvert bottom) would be reconstructed on top of these two layers. Materials Engineering and Testing Services (METS) of the Division of Engineering Services, Caltrans expressed concerns that this alternative would not provide enough structural integrity. This alternative was rejected as it would not address the purpose and need of the project.

## **2.4 List of Permits/Approvals Required**

The following approvals or permits are required under the proposed project description:

- Approval from the United States Forest Service is required for this project because the project site is located in the Angeles National Forest. The United States Forest Service is the acting federal lead agency for this proposed project.
- A 404 Permit is required from the Army Corps of Engineers under the Clean Water Act for any dredge or fill activities that take place in jurisdictional Waters of the U.S.
- A 401 Permit is required from the Regional Water Quality Control Board as stated under the Clean Water Act.
- Coordination with the California Department of Fish and Game in regards to a 1601 Streambed Alteration agreement.
- Coordination with the U.S. Department of Fish and Wildlife in regards to possible mitigation requirements to avoid species impacts.

### 3 AFFECTED ENVIRONMENT

#### 3.1 Physical Environment

The proposed culvert rehabilitation project site is on State Route 39 at KP 36.14 (PM 22.46), at Brown's Gulch, in the San Gabriel River Ranger District of the Angeles National Forest. The project site is north of the Morris Reservoir and southwest of the San Gabriel Reservoir. The project area is located at an elevation of 1,619 ft above Mean Sea Level (MSL).

Brown's Gulch is a small, moderately steep sided, bowl-like canyon or gulch which flows into the main San Gabriel Canyon from the west just below the San Gabriel Dam. It is approximately 130ft deep relative to the highway.

#### 3.2 Biological Resources

##### Vegetation

The project area is rural and composed mostly of native vegetation. It is for the most part, dry, rocky, and shrubby. Inside Brown's Gulch at the mouth of the culvert there exists an intermittent stream.

The ecological community on the above mentioned west facing Brown's Gulch canyon side, where the proposed permanent access road is to be constructed, has recently burned. It now consists of an emerging Ceanothus Chaparral Habitat, intermixed with Coastal Scrub plants, annual grasses, riparian and other types of vegetation. Immediately adjacent to the natural slope drainage is a south facing canyon wall (Figure 2). Both areas of the project site include the following species of vegetation:

##### Coastal Scrub Species Present:

California Sage Brush (*Artemisia Californica*)  
Golden Yarrow (*Eriophyllum conferiflorum*)  
Laurel Sumac (*Malosma laurina*)\*  
Bush Monkey Flower (*Mimulus aurantiacus*)

##### Chaparral Species:

California Lilac (*Ceanothus thyrsiflorus*)\*\*  
Deer Brush (*Ceanothus intergerimus*)\*\*  
Birch-leaf Mountain Mahogany (*Cercocarpus betuloides*)\*  
California Ash (*Fraxinus dipetata*)  
Saw-toothed Goldenbush (*Hazardia squarrosa*)\*  
Toyon (*Heteromeles arbutifolia*)  
Chia (*Salvia columbariae*)\*\*

##### Coastal Scrub/Chaparral Species:

California Buckwheat (*Eriogonum fasciculatum*)\*  
Deerweed (*Lotus scoparius*)  
Hollyleaf Cherry (*Prunus ilicifolia*)\*  
Our Lord's Candle (*Yucca whipplei*)\*

**Grassland Species (Annual Grasses)**

Wild Oats (*Avena fatua*)

Brome Grass (*Bromus diandrus*)

**Riparian:**

Mugwort (*Artemisia douglasiana*)

\*These species are characteristic of Ceanothus Chaparral Communities

\*\*Other Ceanothus and Salvia species are characteristic of Ceanothus Chaparral Communities

The disposal/borrow sites for needed fill material can be classified as mostly disturbed Chaparral communities, which lacks much vegetation since Caltrans drives heavy equipment to bring and take fill material to and from project sites. There is a mature coast live oak (*Quercus agrifolia*) at the borrow site located at PM 21.04.

**Intermittent Stream**

The intermittent stream that flows south at the base of Brown's Gulch is dry most of the year. The streambed is surrounded by riparian vegetation on both sides. This intermittent stream stems from four other intermittent streams which originate more than a mile northwest of the project site between Pine Mountain and Polecat Gulch. The stream then flows thru Brown's Gulch, continuing south through the culvert under the highway and into the main San Gabriel Canyon just below the San Gabriel Dam. The natural drainage that flows from the edge of the highway down to the culvert mouth also adds to this system.

## 4 ENVIRONMENTAL EVALUATION

Basic guidance for determining the significance of project impacts is given by Title 14 of the California Code of Regulations Section 15064, and the checklist below. These resources assist in identifying the need for mitigation requirement development in order to reduce possible project effects to a level of less than significant. It is with this evaluation that the decision to prepare an Initial Study was made.

The environmental factors checked below would be potentially affected by this project.

### ENVIRONMENTAL FACTORS POTENTIALLY AFFECTED:

- |  |   |   |
|--|---|---|
| <input type="checkbox"/> Aesthetics                      | <input type="checkbox"/> Agriculture Resources              | <input type="checkbox"/> Air Quality            |
| <input checked="" type="checkbox"/> Biological Resources | <input type="checkbox"/> Cultural Resources                 | <input type="checkbox"/> Geology /Soils         |
| <input type="checkbox"/> Hazards & Hazardous Materials   | <input type="checkbox"/> Hydrology / Water Quality          | <input type="checkbox"/> Land Use / Planning    |
| <input type="checkbox"/> Mineral Resources               | <input type="checkbox"/> Noise                              | <input type="checkbox"/> Population / Housing   |
| <input type="checkbox"/> Public Services                 | <input type="checkbox"/> Recreation                         | <input type="checkbox"/> Transportation/Traffic |
| <input type="checkbox"/> Utilities / Service Systems     | <input type="checkbox"/> Mandatory Findings of Significance |   |



## 4.1 AESTHETICS

	Potentially Significant Impact	Less Than Significant with Mitigation Incorporation	Less Than Significant Impact	No Impact
<b>Would the project:</b>				
a) Have a substantial adverse effect on a scenic vista?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
b) Substantially damage scenic resources, including, but not limited to, trees, rock outcroppings, and historic buildings within a state scenic highway?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
c) Substantially degrade the existing visual character or quality of the site and its surroundings?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
d) Create a new source of substantial light or glare, which would adversely affect day or nighttime views in the area?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

### 4.1.1 Discussion of Environmental Evaluation Question 4.1 – Aesthetics

This project proposes to install a permanent access ramp from the road elevation down a steep incline into Brown's Gulch terminating at the mouth of the existing culvert that requires maintenance. Most of the construction involved would not be visible from SR-39. The access ramp would be located on the west-side of SR-39 would be hydro-seeded with native vegetation once the rehabilitation of the culvert is completed. Therefore, there would be no visual impacts associated with the ramp construction. The addition of the access ramp would have a less than significant impact on the visual quality of the site because only a small portion of the access ramp would be visible from the roadside. The proposed project is not expected to create any new light or glare which would adversely affect day or nighttime views in the area.

### 4.1.2 Measures to Minimize Harm

Hydro seeding of the completed access ramp has been proposed to maintain the integrity of visual aesthetics in the area.

## 4.2 AGRICULTURE RESOURCES

In determining whether impacts to agricultural resources are significant environmental effects, lead agencies may refer to the California Agricultural Land Evaluation and Site Assessment Model (1997) prepared by the California Dept. of Conservation as an optional model to use in assessing impacts on agriculture and farmland.

Potentially Significant Impact	Less Than Significant with Mitigation Incorporation	Less Than Significant Impact	No Impact
--------------------------------	---	------------------------------	-----------

Would the project:

a) Convert Prime Farmland, Unique Farmland, or Farmland of Statewide Importance (Farmland), as shown on the maps prepared pursuant to the Farmland Mapping and Monitoring Program of the California Resources Agency, to non-agricultural use?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
b) Conflict with existing zoning for agricultural use, or a Williamson Act contract?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
c) Involve other changes in the existing environment which, due to their location or nature, could result in conversion of Farmland, to non-agricultural use?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

### 4.2.1 Discussion of Environmental Evaluation Question 4.2 – Agricultural Resources

The project site is located within the U.S. Angeles National Forest. The land is zoned for open space; therefore, no impacts to agricultural land will occur.

### 4.2.2 Measures to Minimize Harm

None required.

### 4.3 AIR QUALITY

Where available, the significance criteria established by the applicable air quality management or air pollution control district may be relied upon to make the following determinations. Would the project:

Would the project:

	Potentially Significant Impact	Less Than Significant with Mitigation Incorporation	Less Than Significant Impact	No Impact
a) Conflict with or obstruct implementation of the applicable air quality plan?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
b) Violate any air quality standard or contribute substantially to an existing or projected air quality violation?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
c) Result in a cumulatively considerable net increase of any criteria pollutant for which the project region is non-attainment under an applicable federal or state ambient air quality standard (including releasing emissions, which exceed quantitative thresholds for ozone precursors)?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
d) Expose sensitive receptors to substantial pollutant concentrations?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
e) Create objectionable odors affecting a substantial number of people?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

#### 4.3.1 Discussion of Environmental Evaluation Question 4.3 – Air Quality

The proposed project is described as an HA – 42 (Protective Betterment) project and would not increase traffic or highway capacity. Therefore, there would be no long-term effects on air quality as a result of this project. No significant adverse air quality impacts would result from construction activities or operational activities associated with this project.

#### 4.3.2 Measures to Minimize Harm

The following standard measures would be followed in order to ensure that the potential for any impacts to air quality would be reduced during construction:

- All clearing, grubbing, grading, earth moving, or excavation activities would cease during periods of high winds to prevent excessive amounts of fugitive dust.
- All trucks that haul excavated or grade materials on or off site would comply with the State Vehicle Code Section 23114.
- Active portions off -site and unpaved on-site or off-site (disposal sites) roads shall be periodically watered with environmentally safe dust suppressant to prevent excessive amounts of dust.
- On-site (including disposal site) vehicle speed shall not exceed 15 miles per hour.
- The contractor shall cease grading and excavation activities when wind speeds exceed 25 miles per hour and during Stage III Smog Alerts.

- Construction equipment engines shall be maintained in good condition and in proper tune as per manufacturers' specifications to maximize efficiency and minimize emissions.

#### 4.4 BIOLOGICAL RESOURCES

	Potentially Significant Impact	Less Than Significant with Mitigation Incorporation	Less Than Significant Impact	No Impact
<b>Would the project:</b>				
a) Have a substantial adverse effect, either directly or through habitat modifications, on any species identified as a candidate, sensitive, or special status species in local or regional plans, policies, or regulations, or by the California Department of Fish and Game or U.S. Fish and Wildlife Service?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
b) Have a substantial adverse effect on any riparian habitat or other sensitive natural community identified in local or regional plans, policies, regulations or by the California Department of Fish and Game or US Fish and Wildlife Service?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
c) Have a substantial adverse effect on federally protected wetlands as defined by Section 404 of the Clean Water Act (including, but not limited to, marsh, vernal pool, coastal, etc.) through direct removal, filling, hydrological interruption, or other means?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
d) Interfere substantially with the movement of any native resident or migratory fish or wildlife species or with established native resident or migratory wildlife corridors, or impede the use of native wildlife nursery sites?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
e) Conflict with any local policies or ordinances protecting biological resources, such as a tree preservation policy or ordinance?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
f) Conflict with the provisions of an adopted Habitat Conservation Plan, Natural Community Conservation Plan, or other approved local, regional, or state habitat conservation plan?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

##### 4.4.1 Discussion of Environmental Evaluation Question 4.4 – Biological Resources

- a.) Listed and sensitive plant and animal species may have the potential to occur in the same general area as the project according to the State (CDFG) and Federal (USDAFS and USFWS) species list databases, and habitat model maps. However, there are no documented occurrences of any listed or sensitive plant or animal species within the project area itself. Biological surveys were conducted in 2001 and 2002. After evaluation and analysis, the field data and biological studies concluded



that all listed and sensitive plant and animal species, as well as their respective habitats were deemed absent from the project area.

### Plants

#### STATE – CDFG California Natural Diversity Database (CNDDB)

- Robinson's pepper-grass (*Lepidium virginicum* var *robinsonii*)
- San Gabriel Mountains dudleya (*Dudleya densiflora*)
- many-stemmed dudleya (*Dudleya multicaulis*)
- thread-leaved brodiaea (*Brodiaea filifolia*)
- Plummer's mariposa lily (*Calochortus plummerae*)

#### FEDERAL – USDAFS Plant Habitat Models & USFWS Listed Species

- Braunton's milk vetch (*Astragalus brauntonii*)
- Nevin's barberry (*Berberis nevinii*)
- Thread-leaved brodiaea (*Brodiaea filifolia*)

Studies concluded that listed or sensitive plant species do not occur within the project area. No suitable habitat for these species was found within the project area. Indirect impacts to these species possibly occurring in adjacent areas are not anticipated. There is the possibility of transporting weeds and/or non-native plant seeds to the project area from the borrow sites. Measures to Minimize Harm would be implemented to reduce this risk. At borrow site #2 there exists a mature oak tree. Any kind of grade change can seriously damage an oak tree. Implementing suggested Measures to Minimize Harm should avoid impacts to this mature oak tree. The expected disturbances (noise and dust) to adjacent areas would be temporary and measures to minimize harm would be implemented. Therefore, the proposed action is not expected to impact any state or federally listed, or U.S. Forest Service sensitive plant species.

### Birds

#### STATE – CDFG California Natural Diversity Database (CNDDB)

- None

#### FEDERAL – USDAFS Bird Habitat Models & USFWS Listed Species

- least Bell's vireo (*Virea bellii pusillus*)
- California gnatcatcher (*Polioptila californica californica*)
- southwestern willow flycatcher (*Empidonax traillii extimus*)
- bald eagle (*Haliaeetus leucocephalus*)

Loss of nesting sites, nesting habitat, and/or loss of nesting birds or eggs directly caused by vegetation clearing and construction activities, are possible project impacts. Noise associated with construction could result in an indirect impact by interrupting the communication process as well as the nesting and fledging success rates of nearby nesting and fledging birds. Studies concluded that listed

or sensitive bird species do not occur within the project area. These species respective habitats were also deemed absent from the project area.

### Mammals

STATE – CDFG California Natural Diversity Database (CNDDB)

- Nelson's bighorn sheep (*Ovis canadensis nelsoni*)

FEDERAL – USDAFS Mammal Habitat Models & USFWS Listed Species

- None

Studies concluded that listed or sensitive mammal species in the area of the project site. No suitable habitat for these species was found within the project area. All potential disturbances (noise and dust) due to construction activities will be temporary and will be greatly reduced by the Measures to Minimize Harm. Therefore, no impact to any state or federally listed, or U.S. Forest Service sensitive mammal species would result from the proposed project.

### Amphibians

STATE – CDFG California Natural Diversity Database (CNDDB)

- Coast range newt (*Taricha torosa torosa*)
- Mountain yellow-legged frog (*Rana muscosa*)

FEDERAL – USDAFS Amphibian Habitat Models & USFWS Listed Species

- arroyo southwestern toad (*Bufo microscaphus californicus*)
- California red legged frog (*Rana aurora draytoni*)

There are no document occurrences of any listed or sensitive amphibian species within the proposed project area. Studies concluded that listed and sensitive amphibian species, as well as their respective habitats, were deemed absent from the project area. Thus direct effects to the above referenced sensitive amphibian species is not anticipated. Indirect effects with regards to construction would not be anticipated either due to the lack of presence of these species. Implementing the planned Measures to Minimize Harm will minimize any noise, dust and impacts to water quality that might occur during construction.

### Reptiles

STATE – CDFG California Natural Diversity Database (CNDDB)

- southwestern pond turtle (*Clemmys marmorata pallida*)
- San Diego coast horned lizard (*Phrynosoma coronatum blainvillei*)
- two-striped garter snake (*Thamnophis hammondi*)

Biological surveys were conducted in 2001 and 2002. They concluded that no listed or sensitive reptile species occur within the project area. Appropriate habitat for sensitive reptile species previously noted was also deemed absent. The measures to minimize harm will ensure that the proposed action does not adversely impact water quality, which in turn could affect reptiles. Noise and dust generated from construction activities will be temporary and is not expected to have impacts since no listed or sensitive reptile species occur within the project area.

### **Fish**

#### **STATE – CDFG California Natural Diversity Database (CNDDB)**

- Arroyo chub (*Gila orcutti*)
- Santa Ana speckled dace (*Thinichthys osculus*)
- Santa Ana sucker (*Catostomus santaanae*)

#### **FEDERAL – USDAFS Fish Habitat Models & USFWS Listed Species**

- Arroyo chub (*Gila orcutti*)
- Santa Ana Speckled Dace (*Rhinichthys osculus*)

Biological surveys were conducted in 2001 and 2002. Studies concluded that no listed or sensitive fish species occur within the project area. Appropriate habitats were not present either. Impacts associated with noise, dust and possible impacts to water quality are not expected once Measures to Minimize Harm are implemented. Thus implementation of the proposed action will not result in the modification and/or loss of habitats potentially utilized by listed or sensitive fish species.

### **Habitats**

#### **STATE – CDFG California Natural Diversity Database (CNDDB)**

- Southern California Arroyo chub/Santa Ana sucker stream
- Riversidian alluvial fan sage scrub
- Southern coast live oak riparian

The project area is comprised of an emerging Ceanothus Chaparral Habitat, intermixed with Coastal Scrub plants, annual grasses, riparian and other types of vegetation. This project is anticipated to impact less than 0.409 acres of Ceanothus Chaparral Habitat, and less than 0.31397 acres of Coastal Scrub Habitat, in the San Gabriel Mountains.

None of the above sensitive habitats are present within the project area. Therefore, no impacts to the above state listed or sensitive habitats would be a result of the proposed project.

- b.) The proposed project would not have a substantial adverse effect on riparian or other sensitive habitat. The vegetation that would be removed as a result of this project would be mitigated for by implementing Measures to Minimize Harm. The

implementation of the outlined mitigation measures will result in the effects on the local habitat being less than significant.

- c.) A wetland delineation was conducted at the project site on October 22, 2002. Two soil pits were dug near the culvert mouth (Site #'s 1 and 2 – See Appendix H). Site #1 did not exhibit hydric soils, wetland hydrology, or hydrophytic vegetation. It was thus concluded that Site #1 is not a State or Federal Wetlands. Site #2 did not exhibit hydric soils or hydrophytic vegetation. Wetland hydrology appeared to be present, and thus Site #2 may qualify to be a State Wetlands. The acreage of wetland loss or impact has been identified as being 0.1 acres. These impacts to wetlands are considered temporary since mitigation measures will restore and enhance the project site to at least its pre-construction habitat value.
- d.) The proposed project area does not offer much value as a wildlife corridor because the culvert is approximately 600 ft. long and completely dark between the mouth and its end. The culvert bottom is badly eroded and has a 30 ft. drop off at the end. The project is not anticipated to pose a permanent impact to the movement of native resident or migratory fish or wildlife species since construction will only be temporary (4 months) and the culvert will only be rehabilitated, not blocked, altered, or removed.
- e.) The project is located within the Angeles National Forest. Coordination with the Forest Service has been conducted to ensure the proposed project would not conflict with any policies or regulations pertaining to biological regulations.
- f.) The proposed project would not conflict with the provisions of an adopted Habitat Conservation Plan, Natural Community Conservation Plan, or other approved local, regional, or state habitat conservation plan.

#### 4.4.2 Measures to Minimize Harm

##### Vegetation and Wildlife

- The vegetation that would be removed in order to create the access path will be hydro-seeded with native grasses and shrubs for the purpose of erosion control and vegetation replacement after construction. The following will be included in the hydro-seed mix:

deer weed ( <i>Lotus scoparius</i> )	Mugwort ( <i>Artemisia douglasiana</i> )
California sage brush ( <i>Artemisia californica</i> )	California buckwheat ( <i>Eriogonum fasciculatum</i> )
Toyon ( <i>Heteromeles arbutifolia</i> )	Laurel sumac ( <i>Malosma laurina</i> )
bush monkey flower ( <i>Mimulus aurantiacus</i> )	Our lord's candle ( <i>Yucca whipplei</i> )
deer brush ( <i>Ceanothus intergerimus</i> )	Deer grass ( <i>Muhlenbergia rigens</i> )
chia ( <i>Salvia columbariae</i> )	Parry's phacelia ( <i>Phacelia parryi</i> )

- All native trees removed shall be replaced at a 10:1 ratio. Caltrans proposes to plant approximately:

50 big leaf maple (*Acer macrophyllum*)

100 birch-leaf mahogany (*Cercocarpus betuloides*)

50 western sycamores (*Platanus racemosa*)

100 scrub oaks (*Quercus berberidifolia*)

100 arroyo willows (*Salix lasiolepis*): Cuttings from the willows at the project site

50 white alder (*Alnus rhombifolia*)

- The top 6" upper crust/top soil of fill from the borrow sites shall be skimmed and stock piled at the borrow site, rather than being used as fill at the Culvert Rehabilitation Site. This will reduce any possibility of transporting weeds and/or non-native plant seeds to the Culvert Rehabilitation site, where the native vegetation hydro-seeding shall take place.
- Vegetation shall be cleared and grubbed only within the excavation and embankment slope lines at the culvert site. Adjacent canyons/hillsides and existing vegetation outside the areas to be cleared, grubbed, borrowed, filled, and graded will be avoided.
- The borrow sites shall be fenced to protect adjacent vegetation and hillsides. Impact to any adjacent vegetation, rocks, or terrain outside of the fenced area will be prohibited. These fences shall be approved by a District Biologist prior to removal of any fill.
- If plant species outside the permanent impact area must be cleared, they shall be cut above ground to allow for re-sprouting.
- The area adjacent to the existing oak tree at borrow site #2 will be excavated; there is no proposed embankment at this location. Excavation will be limited to areas outside the drip line, plus 1/3 of the radius of the drip line and outside of any visible roots. Said excavation will have a slope of 2:1 or flatter away from the tree. Furthermore, the oak shall also be fenced 3 feet (1m) beyond the drip line. No soil or vegetation disturbance shall take place within the fenced area. All these activities shall also be coordinated with both the Division of Environmental Planning and the Office of Landscape Architecture.
- Since construction is scheduled to take place within the bird-nesting season (March 1<sup>st</sup> – September 1<sup>st</sup>), all affected vegetation shall be cut above ground prior to the nesting season in order to prohibit the initiation of nesting.
- If any sensitive biological resources are found during construction, all activities shall cease until the district biologist and the appropriate resource agencies are contacted to review options. A district biologist will survey the appropriate areas for nesting birds a minimum of once every ten days. The surveys will concentrate on areas where there are adjacent trees, where nesting birds are potentially located. If nesting birds are found, the area shall be flagged and a buffer zone will be established where work would be prohibited.
- The omission of pile driving activities will minimize any effect from construction noise on any State or Federal Listed or U.S. Forest Service Sensitive bird species.

### Wetlands

- In addition to the proposed revegetation listed above, a concentrated area of mugwort hydroseeding would take place at the toe of the canyon where it is currently the dominant vegetation at this location.



## **Water Quality**

- All work will be conducted outside of the rain season (Oct 1<sup>st</sup> – March 30<sup>th</sup>), except for the cutting of the above mentioned potential nesting vegetation which will be done prior to February 15<sup>th</sup>.
- Best storm water pollution control management practices will be implemented to protect the Construction Zone from local flooding and to prevent contaminated runoff or prevent excessive silt and other erosion from entering the Culvert or any other drainage. Sandbag barriers, check dams, sediment traps, and other erosion control measures will be provided as needed, with the understanding that all must be placed inside the project area (study area or “footprint”). If any devices must be placed outside the project area, a re-evaluation may be necessary.
- Raw cement/concrete or washings thereof, asphalt, paint, oil/other petroleum products, or any other substances which could be hazardous to aquatic life, resulting from project related activities, shall be prevented from contaminating the soil and/or entering the culvert or any drainages.
- A Storm Water Pollution Prevention Plan (SWPPP) and Water Pollution Control Plan (WPCP) will be developed and implemented for the project including above items as required during the year. The SWPPP permit will be required from the Regional Water Quality Control Board.
- Erosion control will be provided as stipulated above.
- The following permits will be obtained through coordination with the appropriate agency:
  - 1601 Streambed Alteration Agreement (California Department of Fish and Game)
  - 404 Permit (U.S. Army Corps of Engineers)
  - 401 Permit (California Regional Water Quality Control Board)

All provisions required by these permits will be incorporated into the project specifications, and a mutually acceptable mitigation plan will be prepared. Coordination with these agencies shall be ongoing to ensure that impacts to the drainage, perennial stream, and riparian vegetation are adequately mitigated.

## **Construction Site: Dust, Equipment, and Litter**

- At the start of each workday before moving mechanical equipment, the contractor and maintenance personnel shall look under equipment for animals (reptiles, amphibians, and mammals) that may use the equipment for cover.
- Maintenance and construction equipment shall be checked and maintained daily by the contractor so as to prevent leaks or other potential contamination problems.
- At the end of the day when operations are complete debris or trash shall be removed from the work area and properly disposed of by the contractor. All personnel working within the project area will follow all litter and pollution laws.
- The contractor shall apply water or dust palliative to graded areas for the alleviation or prevention of dust nuisance.
- There shall be daily removal of any dirt that spills onto the paved roads.

- The contractor shall require the covering of all haul trucks.
- Construction storage will be in a designated non-sensitive area. Construction equipment will be stored outside of the channel (defined as top of slope to top of slope), away from the stream banks. No equipment maintenance will be performed in the streambed.
- The perimeter of the construction area will be fenced and flagged to prevent damage to the adjacent area.
- Pre-construction surveys will be conducted to determine the presence or absence of State/Federal Listed species or U.S. Forest Service Sensitive Species likely to occur in the area. If any sensitive species are found, protective measures will be developed in coordination with the appropriate resource agencies to protect these species.
- To avoid impacts to sensitive wildlife species in surrounding areas, construction activities will be limited to daylight hours.
- To avoid impacts to sensitive wildlife species in surrounding areas, construction areas will not be lighted during non-daylight hours.

## 4.5 CULTURAL RESOURCES

	Potentially Significant Impact	Less Than Significant with Mitigation Incorporation	Less Than Significant Impact	No Impact
<b>Would the project:</b>				
a) Cause a substantial adverse change in the significance of a historical resource as defined in '15064.5?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
b) Cause a substantial adverse change in the significance of an archaeological resource pursuant to '15064.5?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
c) Directly or indirectly destroy a unique paleontological resource or site or unique geologic feature?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
d) Disturb any human remains, including those interred outside of formal cemeteries?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

### 4.5.1 Discussion of Environmental Evaluation Question 4.5 – Cultural Resources

The culvert at Browns' Gulch was built in April 1932. The structure is not listed on the National Register of Historic Places. The Historical Property Survey Report (HPSR) dated March 8, 2001, confirmed that the culvert structure did not have architectural or historic features which would make it eligible for the National Register. No known archaeological resources would be affected by the proposed project. This determination was made after an archaeological records search at the South Central Coastal Information Center of the California Historical Resources Information System at the California State University, Fullerton, a Forest Service records search, a field reconnaissance visit, and a review of Caltrans files was completed. There would be no known historical or cultural resource impacts associated with the proposed project.

### 4.5.2 Measures to Minimize Harm

Should subsurface archaeological materials, cultural materials or human remains be encountered during construction activities, Caltrans' cultural resources policy requires that work be halted immediately in the area of the find(s) until they can be evaluated by a qualified archaeologist (Caltrans Environmental Handbook, Volume 2, Chapter 7, Section 7-8).

## 4.6 GEOLOGY AND SOILS

	Potentially Significant Impact	Less Than Significant with Mitigation Incorporation	Less Than Significant Impact	No Impact
<b>Would the project:</b>				
a) Expose people or structures to potential substantial adverse effects, including the risk of loss, injury, or death involving:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
i) Rupture of a known earthquake fault, as delineated on the most recent Alquist-Priolo Earthquake Fault Zoning Map issued by the State Geologist for the area or based on other substantial evidence of a known fault? Refer to Division of Mines and Geology Special Publication 42.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
ii) Strong seismic ground shaking?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
iii) Seismic-related ground failure, including liquefaction?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
iv) Landslides?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
b) Result in substantial soil erosion or the loss of topsoil?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
c) Be located on a geologic unit or soil that is unstable, or that would become unstable as a result of the project, and potentially result in on- or off-site landslide, lateral spreading, subsidence, liquefaction or collapse?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
d) Be located on expansive soil, as defined in Table 18-1-B of the Uniform Building Code (1994), creating substantial risks to life or property?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
e) Have soils incapable of adequately supporting the use of septic tanks or alternative waste water disposal systems where sewers are not available for the disposal of waste water?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

### 4.6.1 Discussion of Environmental Evaluation Question 4.6 – Geology and Soils

The project site is located in the San Gabriel Mountains, which is part of the Transverse Ranges Geomorphic Province. The rock outcrops in the area display predominately gray-black banded gneiss or metamorphic rock. Soils covering the rocks are usually very thin. There is no known earthquake fault crossing the site. The closest earthquake

fault is the Sierra Madre – Raymond Hill Fault system, located approximately 13.5 km southwest of the site. Seismic ground shaking could possibly cause some structural damage to the culvert. Rock fall due to ground shaking could occur as well. However, since reconstruction of the bottom of the existing culvert would be confined, this earthquake phenomenon does not represent any hazard to the site.

Potential seismic hazard of ground rupture or liquefaction of the site is unlikely.

The construction of this project would not be precluded by any geological or geotechnical conditions. This project would have no adverse effect on the existing environmental conditions.

#### **4.6.2 Measures to Minimize Harm**

- Embankment construction should conform to Section 19 of the Standard Specifications.
- The use of artificially contrived (geosynthetic) soil or earth reinforcement is recommended.



## 4.7 HAZARDS AND HAZARDOUS MATERIALS

	Potentially Significant Impact	Less Than Significant with Mitigation Incorporation	Less Than Significant Impact	No Impact
<b>Would the project:</b>				
a) Create a significant hazard to the public or the environment through the routine transport, use, or disposal of hazardous materials?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
b) Create a significant hazard to the public or the environment through reasonably foreseeable upset and accident conditions involving the release of hazardous materials into the environment?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
c) Emit hazardous emissions or handle hazardous or acutely hazardous materials, substances, or waste within one-quarter mile of an existing or proposed school?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
d) Be located on a site which is included on a list of hazardous materials sites compiled pursuant to Government Code Section 65962.5 and, as a result, would it create a significant hazard to the public or the environment?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
e) For a project located within an airport land use plan or, where such a plan has not been adopted, within two miles of a public airport or public use airport, would the project result in a safety hazard for people residing or working in the project area?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
f) For a project within the vicinity of a private airstrip, would the project result in a safety hazard for people residing or working in the project area?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
g) Impair implementation of or physically interfere with an adopted emergency response plan or emergency evacuation plan?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
h) Expose people or structures to a significant risk of loss, injury or death involving wildland fires, including where wildlands are adjacent to urbanized areas or where residences are intermixed with wildlands?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

#### **4.7.1 Discussion of Environmental Evaluation Question 4.7 – Hazards and Hazardous Material**

There is no potential of hazardous waste contamination or aerially deposited lead (ADL) contaminated soil due to the low Average Daily Traffic (ADT) on SR-39. All fill material required for this project would be retrieved from local disposal sites, which are comprised of native material that falls onto the roadway from adjacent slopes. This should ensure that no hazardous material would be brought in from an outside source. Therefore, no hazardous waste impacts associated with the proposed project are expected.

This proposed project is located within the U.S. Forest Service. While wildland fires in this setting are a possible threat, the actions under this proposed project would not significantly increase the risk of loss, injury or death as a result of wildland fires. Therefore, adjacent urbanized areas or residences are not at a greater risk as a result of the proposed actions.

#### **4.7.2 Measures to Minimize Harm**

The following measures will be followed to further enhance safety during construction:

- A fire prevention and control program will be established that limits activity in and adjacent to flammable vegetation. A full water truck should be available should a fire occur within the project area.
- Should excavation reveal unknown potentially hazardous materials, Caltrans' policy requires work to halt in the vicinity until the area in question is investigated and proper mitigation is proposed.

## 4.8 HYDROLOGY AND WATER QUALITY

	Potentially Significant Impact	Less Than Significant with Mitigation Incorporation	Less Than Significant Impact	No Impact
<b>Would the project:</b>				
a) Violate any water quality standards or waste discharge requirements?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
b) Substantially deplete groundwater supplies or interfere substantially with groundwater recharge such that there would be a net deficit in aquifer volume or a lowering of the local groundwater table level (e.g., the production rate of pre-existing nearby wells would drop to a level which would not support existing land uses or planned uses for which permits have been granted)?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
c) Substantially alter the existing drainage pattern of the site or area, including through the alteration of the course of a stream or river, in a manner which would result in substantial erosion or siltation on- or off-site?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
d) Substantially alter the existing drainage pattern of the site or area, including through the alteration of the course of a stream or river, or substantially increase the rate or amount of surface runoff in a manner which would result in flooding on- or off-site?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
e) Create or contribute runoff water which would exceed the capacity of existing or planned stormwater drainage systems or provide substantial additional sources of polluted runoff?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
f) Otherwise substantially degrade water quality?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
g) Place housing within a 100-year flood hazard area as mapped on a federal Flood Hazard Boundary or Flood Insurance Rate Map or other flood hazard delineation map?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
h) Place within a 100-year flood hazard area structures which would impede or redirect flood flows?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
i) Expose people or structures to a significant risk of loss, injury or death involving flooding, including flooding as a result of the failure of a levee or dam?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
j) Inundation by seiche, tsunami, or mudflow?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

#### **4.8.1 Discussion of Environmental Evaluation Question 4.8 – Hydrology and Water Quality**

This project involves the maintenance of an existing culvert drainage. Maintaining this culvert would uphold any current water quality standards or waste discharge requirements. Groundwater supplies or recharge would not be impacted by the proposed project. The same drainage pattern of the site would remain, reducing the likelihood of substantial erosion or siltation on- or off-site. Maintaining the culvert would also result in full utility of the drainage capacity for the planned drainage system in the area. No significant amount of excess runoff would be created as a result of the proposed project; therefore, there would be no impact to the capacity of the existing or planned stormwater drainage system.

Brown's Gulch is an intermittent stream, which is dry several months out of the year. The proposed project is located in a non-flood hazard area. Therefore, no impacts associated with flooding would result from the proposed project. Inundation by seiche, tsunami, or mudflow is not expected.

#### **4.8.2 Measures to Minimize Harm**

- All work will be conducted outside of the rainy season (Oct 1 – March 30). If it rains during the construction period, construction shall be halted until flows subside to prevent adverse water quality impacts.
- Best Management Practices will be implemented to protect the project area from local flooding and to prevent contaminated runoff or excessive silt and other sediment from entering the culvert or any other drainage. Sandbag barriers, check dams, sediment traps, and other erosion control measures will be provided.
- Raw cement/concrete or washings thereof, asphalt, paint, oil/other petroleum products, or any other substances which could be hazardous to aquatic life, shall be prevented from contaminating the soil and/or entering the culvert or any drainages.
- A Storm Water Pollution Prevention Plan (SWPPP) and erosion control plan is required. This plan should incorporate recommendations and approval from the Regional Water Quality Control Board (RWQCB). These plans will be submitted to the Resident Engineer (RE) for approval.
- The recommendations given by the administrators of the following permits will be required as part of the SWPPP for this project:
  - 1.) Section 401 Permit of the Clean Water Act administered by the California Regional Water Quality Control Board
  - 2.) Section 404 Permit of the Clean Water Act administered by the U.S. Army Corps of Engineers
  - 3.) 1601 Streambed Alteration agreement administered by the California Department of Fish and Game

## 4.9 LAND USE AND PLANNING

	Potentially Significant Impact	Less Than Significant with Mitigation Incorporation	Less Than Significant Impact	No Impact
<b>Would the project:</b>				
a) Physically divide an established community?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
b) Conflict with any applicable land use plan, policy, or regulation of an agency with jurisdiction over the project (including, but not limited to the general plan, specific plan, local coastal program, or zoning ordinance) adopted for the purpose of avoiding or mitigating an environmental effect?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
c) Conflict with any applicable habitat conservation plan or natural community conservation plan?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

### 4.9.1 Discussion of Environmental Evaluation Question 4.9 – Land Use Planning

The proposed project location is within the U.S. Angeles National Forest. Caltrans is working closely with the U.S. Forest Service in order to make sure this project is consistent with Angeles National Forest future plans. The existing land use of the area is designated as Open Space. The reconstruction of this culvert would be consistent with the Angeles National Forest Land and Resource Management Plan. It would not physically divide an established community, nor does it conflict with any land use plan, policy or regulation of any agency with jurisdiction over the project. The proposed project does not conflict with any applicable habitat conservation plan or natural community conservation plan.

### 4.9.2 Measures to Minimize Harm

None Required.

#### 4.10 MINERAL RESOURCES

	Potentially Significant Impact	Less Than Significant with Mitigation Incorporation	Less Than Significant Impact	No Impact
<b>Would the project:</b>				
a) Result in the loss of availability of a known mineral resource that would be of value to the region and the residents of the state?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
b) Result in the loss of availability of a locally-important mineral resource recovery site delineated on a local general plan, specific plan or other land use plan?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

##### 4.10.1 Discussion of Environmental Evaluation Question 4.10 – Mineral Resources

The proposed project would install an access road and rebuild the existing culvert bottom. No mining activities have taken place within the project area as it is zoned as Open Space; therefore, there are no known mineral resources or mining activities that would be impacted by this project.

##### 4.10.2 Measures to Minimize Harm

None required.



## 4.11 NOISE

	Potentially Significant Impact	Less Than Significant with Mitigation Incorporation	Less Than Significant Impact	No Impact
<b>Would the project result in:</b>				
a) Exposure of persons to or generation of noise levels in excess of standards established in the local general plan or noise ordinance, or applicable standards of other agencies?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
b) Exposure of persons to or generation of excessive groundborne vibration or groundborne noise levels?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
c) A substantial permanent increase in ambient noise levels in the project vicinity above levels existing without the project?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
d) A substantial temporary or periodic increase in ambient noise levels in the project vicinity above levels existing without the project?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
e) For a project located within an airport land use plan or, where such a plan has not been adopted, within two miles of a public airport or public use airport, would the project expose people residing or working in the project area to excessive noise levels?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
f) For a project within the vicinity of a private airstrip, would the project expose people residing or working in the project area to excessive noise levels?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

### 4.11.1 Discussion of Environmental Evaluation Question 4.11 – Noise

No activities that would expose persons or result in the generation of noise levels in excess of standards established in the local general plan or noise ordinance, or applicable standards of other agencies, are expected to result from the proposed project.

Construction of this project would require the use of heavy equipment with high noise level characteristics. Typically, construction equipment ranges from concrete mixers and generators producing noise levels in the 80-decibel range from the source to jackhammers at over 90 decibels. No pile drivers would be used for this project.

Construction activities under the proposed project would be the loudest single noise source in the vicinity of the project during the completion of the access ramp and the culvert

rehabilitation. This noise source would be temporary; therefore, it would not be considered significant. Noise impacts associated with grading and paving activities are not anticipated.

#### **4.11.2 Measures to Minimize Harm**

No measures are required, as noise impacts would be temporary; however, construction activities will be limited to daylight hours to further minimize impacts to nearby wildlife species.

## 4.12 POPULATION AND HOUSING

	Potentially Significant Impact	Less Than Significant with Mitigation Incorporation	Less Than Significant Impact	No Impact
<b>Would the project:</b>				
a) Induce substantial population growth in an area, either directly (for example, by proposing new homes and businesses) or indirectly (for example, through extension of roads or other infrastructure)?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
b) Displace substantial numbers of existing housing, necessitating the construction of replacement housing elsewhere?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
c) Displace substantial numbers of people, necessitating the construction of replacement housing elsewhere?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

### 4.12.1 Discussion of Environmental Evaluation Question 4.12 – Population and Housing

The proposed project would install an access road and rebuild the existing culvert bottom. There would be no population growth or displacement of housing associated with this project.

### 4.12.2 Measures to Minimize Harm

None required.

#### 4.13 PUBLIC SERVICES

	Potentially Significant Impact	Less Than Significant with Mitigation Incorporation	Less Than Significant Impact	No Impact
a) Would the project result in substantial adverse physical impacts associated with the provision of new or physically altered governmental facilities, need for new or physically altered governmental facilities, the construction of which could cause significant environmental impacts, in order to maintain acceptable service ratios, response times or other performance objectives for any of the public services:				
Fire protection?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Police protection?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Schools?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Parks?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Other public facilities?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

##### 4.13.1 Discussion of Environmental Evaluation Question 4.13 – Public Services

No service ratios, response times or other performance objectives for any of the public services listed would be impacted by the proposed culvert maintenance project.

##### 4.13.2 Measures to Minimize Harm

None required.

#### **4.14 RECREATION**

	Potentially Significant Impact	Less Than Significant with Mitigation Incorporation	Less Than Significant Impact	No Impact
a) Would the project increase the use of existing neighborhood and regional parks or other recreational facilities such that substantial physical deterioration of the facility would occur or be accelerated?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
b) Does the project include recreational facilities or require the construction or expansion of recreational facilities which might have an adverse physical effect on the environment?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

##### **4.14.1 Discussion of Environmental Evaluation Question 4.14 – Recreation**

The proposed maintenance of an existing culvert would not impact any recreational facilities in terms of increased use, nor would the project require new or the expansion of such facilities.

##### **4.14.2 Measures to Minimize Harm**

None required.

#### 4.15 TRANSPORTATION/TRAFFIC

	Potentially Significant Impact	Less Than Significant with Mitigation Incorporation	Less Than Significant Impact	No Impact
<b>Would the project:</b>				
a) Cause an increase in traffic which is substantial in relation to the existing traffic load and capacity of the street system (i.e., result in a substantial increase in either the number of vehicle trips, the volume to capacity ratio on roads, or congestion at intersections)?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
b) Exceed, either individually or cumulatively, a level of service standard established by the county congestion management agency for designated roads or highways?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
c) Result in a change in air traffic patterns, including either an increase in traffic levels or a change in location that results in substantial safety risks?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
d) Substantially increase hazards due to a design feature (e.g., sharp curves or dangerous intersections) or incompatible uses (e.g., farm equipment)?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
e) Result in inadequate emergency access?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
f) Result in inadequate parking capacity?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
g) Conflict with adopted policies, plans, or programs supporting alternative transportation (e.g., bus turnouts, bicycle racks)?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

##### 4.15.1 Discussion of Environmental Evaluation Question 4.15 – Transportation/Traffic

The proposed project would install an access road and rebuild an eroded culvert bottom, and would have no impacts to transportation or traffic in the area. During construction standard lane closures would be required.

##### 4.15.2 Measures to Minimize Harm

SR – 39 Highway is more heavily traveled on weekends. In order to minimize the possibility of traffic increases during construction of the access ramp, construction will take place only on weekdays.



#### 4.16 UTILITIES AND SERVICE SYSTEMS

	Potentially Significant Impact	Less Than Significant with Mitigation Incorporation	Less Than Significant Impact	No Impact
<b>Would the project:</b>				
a) Exceed wastewater treatment requirements of the applicable Regional Water Quality Control Board?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
b) Require or result in the construction of new water or wastewater treatment facilities or expansion of existing facilities, the construction of which could cause significant environmental effects?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
c) Require or result in the construction of new storm water drainage facilities or expansion of existing facilities, the construction of which could cause significant environmental effects?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
d) Have sufficient water supplies available to serve the project from existing entitlements and resources, or are new or expanded entitlements needed?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
e) Result in a determination by the wastewater treatment provider, which serves or may serve the project that it has adequate capacity to serve the projects' projected demand in addition to the providers' existing commitments?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
f) Be served by a landfill with sufficient permitted capacity to accommodate the project's solid waste disposal needs?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
g) Comply with federal, state, and local statutes and regulations related to solid waste?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

##### 4.16.1 Discussion of Environmental Evaluation Question 4.16 – Utility and Service Systems

This proposed project would not exceed wastewater treatment requirements of the applicable Regional Water Quality Control Board. No new water, stormwater drainage or wastewater treatment facilities or expansion of existing facilities, which would result in significant environmental effects would be required. The project would not increase the need for water supplies, disposal needs or water capacity facilities. No solid waste would be generated from the proposed project.

#### **4.16.2 Measures to Minimize Harm**

None required.

#### 4.17 MANDATORY FINDINGS OF SIGNIFICANCE

	Potentially Significant Impact	Less Than Significant with Mitigation Incorporation	Less Than Significant Impact	No Impact
a) Does the project have the potential to degrade the quality of the environment, substantially reduce the habitat of a fish or wildlife species, cause a fish or wildlife population to drop below self-sustaining levels, threaten to eliminate a plant or animal community, reduce the number or restrict the range of a rare or endangered plant or animal or eliminate important examples of the major periods of California history or prehistory?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
b) Does the project have impacts that are individually limited, but cumulatively considerable? ("Cumulatively considerable" means that the incremental effects of a project are considerable when viewed in connection with the effects of past projects, the effects of other current projects, and the effects of probable future projects)?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
c) Does the project have environmental effects which will cause substantial adverse effects on human beings, either directly or indirectly?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

##### 4.17.1 Discussion of Environmental Evaluation of Question 4.17 – Mandatory Findings of Significance

The proposed project would install an access road and rebuild the existing culvert bottom. The project does not have the potential to degrade the quality of the environment nor does it have the potential to significantly impact fish habitat, species population, or eliminate important examples of the major periods of California history or prehistory. Cumulative impacts would not apply. The project location is in the Angeles National Forest, which has limited development projects in the adjacent area, this lack of development influences the lack of potential for cumulative impacts. Adverse effects to human beings would not result from this project.

##### 4.17.2 Measures to Minimize Harm

None required.

## **5 CONSULTATION AND COORDINATION**

### **5.1 Scoping**

Under the California Environmental Quality Act (CEQA), there is no formal scoping requirement for projects that require the preparation of an Initial Study (IS). A 30-day scoping period was provided in order to allow agencies, government officials and local community members an opportunity to voice their concerns and interests in the proposed project. A Notice of Scoping/Initiation of Studies was sent to involved agencies, government officials and local residents (See Appendix D). An opportunity for a public hearing if requested was included in this announcement. A public hearing was not requested. The deadline for comments to be received was March 20, 2002. No comments were received after the deadline date. All comments received have been taken into consideration during the preparation of this Initial Study (See Appendix E).

### **5.2 Coordination with Resource Agencies**

Caltrans has coordinated with the California Department of Fish and Game, the U.S. Army Corp of Engineers, the Regional Water Quality control Board, and the U.S. Forest Service about the possible impacts associated with this proposed culvert rehabilitation. Since this is a state funded project on a State Highway, the USDA Forest Service (not the Federal Highway Administration, FHWA) is anticipated to be the lead federal agency under the National Environmental Policy Act (NEPA). The USDA Forest Service will also act as the federal nexus between Caltrans and the U.S. Fish and Wildlife Service. Further coordination with the above listed resource agencies will take place through the permitting process and through construction.

## 6 LIST OF PREPARERS

Adam Sriro Associate Archaeologist	Cultural and Archaeological Review November 29, 2001
Claudia Harbert Associate Environmental Planner	Negative Historical Property Survey Report March 8, 2001
George T. Ghebranious Senior Transportation Engineer	Hazardous Waste Assessment January 28, 2002
Eduardo Aguilar Environmental Planner	Natural Environmental Study Report August 21, 2002
Timothy Tieu Senior Hydraulic Engineer	Hydraulic Study Report July 26, 2002
Paul Caron Office Chief, Division of Environmental Planning	Document Preparation
Amy Pettler Environmental Planner	Document Preparation

## **7 LIST OF APPENDICES**

Appendix A	Preliminary Design Layouts
Appendix B	List of Acronyms
Appendix C	Summary of Measures to Minimize Harm
Appendix D	Scoping Notice
Appendix E	Scoping Comments
Appendix F	Mailing List
Appendix G	Project Location Maps
Appendix H	Project Area of Impact



## ***Appendix A Preliminary Design Layouts***

STATE OF CALIFORNIA  
DEPARTMENT OF TRANSPORTATION  
PROJECT PLANS FOR CONSTRUCTION ON  
STATE HIGHWAY  
IN LOS ANGELES COUNTY  
ABOUT 7.5 KILOMETERS NORTH OF AZUSA  
AT 0.5 KILOMETER NORTH OF PEJSA CANYON BRIDGE

To be supplemented by Standard Plans dated July, 1999

LOCATION OF CONSTRUCTION  
KP 36.14  
PM 22.46

PROPOSED MATERIAL SITE  
SB KP 30.58  
SB PM 19.00

PROPOSED MATERIAL SITE  
SB KP 33.86  
SB PM 21.04

AZUSA

TO WEST COVING

R/R

ROUTE 39

MORRIS RESERVOIR


SAN GABRIEL RESERVOIR

EAST FORK ROAD

TO CRYSTAL LAKE



The State of California or the Office of the Engineer shall not be responsible for the accuracy or completeness of the information contained in this plan sheet.  
Contractor shall bear a wide field of view to the work shall get the proper information.



CHALDAK & STANIS  
REGISTERED CIVIL ENGINEERS  
10000 WILSON AVENUE, SUITE 100  
LOS ANGELES, CALIFORNIA 90024



Project Engineer: Date  
Registered Civil Engineer

Printed: Address: Date:

The Contractor shall possess the Class (or classes) of license as specified in the "Notice to Contractors".

NO SCALE

FOR REDUCED PLANS ORIGINAL  
SCALE IS IN MILLIMETERS  
0 20 40 60 80  
METERS

PROJECT REPORT, ATTACHMENT 2  
CONTRACT NO. 07-4G7004  
CU 07608  
EA 407001


STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION	PROJECT ENGINEER	CHARLES CHILIPALA	CHECKED BY	DATE	REVISOR	DATE	REVISION

**NOTES:**

1. DIMENSIONS OF THE STRUCTURAL SECTIONS ARE SUBJECT TO THE TOLERANCES SPECIFIED IN THE STANDARD SPECIFICATIONS.
2. SUPERELEVATION AS SHOWN OR AS DIRECTED BY THE ENGINEER.
3. FOR EXACT LOCATIONS OF AC DIKE, SEE LAYOUT SHEET.

**TYPICAL STRUCTURAL SECTIONS**

- 1 195 mm AC (TYPE A)
- 2 75 mm AC (MISCELLANEOUS AREAS)



ALL DIMENSIONS ARE IN METERS  
UNLESS OTHERWISE SHOWN

**TYPICAL CROSS SECTIONS**

NO SCALE

Attachment 3a

X-1

FOR REDUCED PLANS ORIGINAL SCALE IS IN MILLIMETERS

CU 07608

EA 407001

DIST	COUNTY	ROUTE	SHEET NO.	TOTAL SHEETS
07	LA	39	35	14

REGISTERED CIVIL ENGINEER

PLANS APPROVAL DATE

THE SEAL OF THE ENGINEER IS THE EVIDENCE OF HIS REGISTRATION AND THE VALIDITY OF HIS SIGNATURE. IT IS THE RESPONSIBILITY OF THE ENGINEER TO MAINTAIN THE SEAL IN FULL FORCE AND EFFECT AT ALL TIMES.

California Seal for a Seal valid to the end of the year 12/31/2010





STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION	PROJECT ENGINEER	CHECKED BY	DATE
BY <i>Charles</i> MAINTENANCE DESIGN	CHARLES CHILPALA	DESIGNED BY	DATE
		REVISOR	DATE

CHARLES CHILPALA

DELETED BY	CHECKED BY
------------	------------

DATE REVISION	
REVISED BY	



## TYPICAL CROSS SECTIONS

NO SCALE

Attachment 3a

**X-2**

EA 4G7001

CU 07608


```

USERNAME => USER
DCM FILE => REQUEST

```

FOR REDUCED PLANS ORIGINAL  
SCALE IS IN MILLIMETERS

10  
 11  
 12  
 13  
 14  
 15  
 16  
 17  
 18  
 19  
 20  
 21  
 22  
 23  
 24  
 25  
 26  
 27  
 28  
 29  
 30  
 31  
 32  
 33  
 34  
 35  
 36  
 37  
 38  
 39  
 40  
 41  
 42  
 43  
 44  
 45  
 46  
 47  
 48  
 49  
 50  
 51  
 52  
 53  
 54  
 55  
 56  
 57  
 58  
 59  
 60  
 61  
 62  
 63  
 64  
 65  
 66  
 67  
 68  
 69  
 70  
 71  
 72  
 73  
 74  
 75  
 76  
 77  
 78  
 79  
 80  
 81  
 82  
 83  
 84  
 85  
 86  
 87  
 88  
 89  
 90  
 91  
 92  
 93  
 94  
 95  
 96  
 97  
 98  
 99  
 100  
 101  
 102  
 103  
 104  
 105  
 106  
 107  
 108  
 109  
 110  
 111  
 112  
 113  
 114  
 115  
 116  
 117  
 118  
 119  
 120  
 121  
 122  
 123  
 124  
 125  
 126  
 127  
 128  
 129  
 130  
 131  
 132  
 133  
 134  
 135  
 136  
 137  
 138  
 139  
 140  
 141  
 142  
 143  
 144  
 145  
 146  
 147  
 148  
 149  
 150  
 151  
 152  
 153  
 154  
 155  
 156  
 157  
 158  
 159  
 160  
 161  
 162  
 163  
 164  
 165  
 166  
 167  
 168  
 169  
 170  
 171  
 172  
 173  
 174  
 175  
 176  
 177  
 178  
 179  
 180  
 181  
 182  
 183  
 184  
 185  
 186  
 187  
 188  
 189  
 190  
 191  
 192  
 193  
 194  
 195  
 196  
 197  
 198  
 199  
 200  
 201  
 202  
 203  
 204  
 205  
 206  
 207  
 208  
 209  
 210  
 211  
 212  
 213  
 214  
 215  
 216  
 217  
 218  
 219  
 220  
 221  
 222  
 223  
 224  
 225  
 226  
 227  
 228  
 229  
 230  
 231  
 232  
 233  
 234  
 235  
 236  
 237  
 238  
 239  
 240  
 241  
 242  
 243  
 244  
 245  
 246  
 247  
 248  
 249  
 250  
 251  
 252  
 253  
 254  
 255  
 256  
 257  
 258  
 259  
 260  
 261  
 262  
 263  
 264  
 265  
 266  
 267  
 268  
 269  
 270  
 271  
 272  
 273  
 274  
 275  
 276  
 277  
 278  
 279  
 280  
 281  
 282  
 283  
 284  
 285  
 286  
 287  
 288  
 289  
 290  
 291  
 292  
 293  
 294  
 295  
 296  
 297  
 298  
 299  
 300  
 301  
 302  
 303  
 304  
 305  
 306  
 307  
 308  
 309  
 310  
 311  
 312  
 313  
 314  
 315  
 316  
 317  
 318  
 319  
 320  
 321  
 322  
 323  
 324  
 325  
 326  
 327  
 328  
 329  
 330  
 331  
 332  
 333  
 334  
 335  
 336  
 337  
 338  
 339  
 340  
 341  
 342  
 343  
 344  
 345  
 346  
 347  
 348  
 349  
 350  
 351  
 352  
 353  
 354  
 355  
 356  
 357  
 358  
 359  
 360  
 361  
 362  
 363  
 364  
 365  
 366  
 367  
 368  
 369  
 370  
 371  
 372  
 373  
 374  
 375  
 376  
 377  
 378  
 379  
 380  
 381  
 382  
 383  
 384  
 385  
 386  
 387  
 388  
 389  
 390  
 391  
 392  
 393  
 394  
 395  
 396  
 397  
 398  
 399  
 400  
 401  
 402  
 403  
 404  
 405  
 406  
 407  
 408  
 409  
 410  
 411  
 412  
 413  
 414  
 415  
 416  
 417  
 418  
 419  
 420  
 421  
 422  
 423  
 424  
 425  
 426  
 427  
 428  
 429  
 430  
 431  
 432  
 433  
 434  
 435  
 436  
 437  
 438  
 439  
 440  
 441  
 442  
 443  
 444  
 445  
 446  
 447  
 448  
 449  
 450  
 451  
 452  
 453  
 454  
 455  
 456  
 457  
 458  
 459  
 460  
 461  
 462  
 463  
 464  
 465  
 466  
 467  
 468  
 469  
 470  
 471  
 472  
 473  
 474  
 475  
 476  
 477  
 478  
 479  
 480  
 481  
 482  
 483  
 484  
 485  
 486  
 487  
 488  
 489  
 490  
 491  
 492  
 493  
 494  
 495  
 496  
 497  
 498  
 499  
 500  
 501  
 502  
 503  
 504  
 505  
 506  
 507  
 508  
 509  
 510  
 511  
 512  
 513  
 514  
 515  
 516  
 517  
 518  
 519  
 520  
 521  
 522  
 523  
 524  
 525  
 526  
 527  
 528  
 529  
 530  
 531  
 532

[illegible]

NO.	$\sigma$	$\Delta$	T	L
1	57,000	27.14.02	13.165	26,000
2	50,000	14.50.43	8.514	12,954
3	10,000	40.0.15	10,000	15,708

**LEGEND**


MS. A. 9. 2 v. 6, p. 20


**LAYOUT** **L-1**







DIST. COUNTY		ROUTE	SHEET NO.	
07	L.A.	39	35	14
REGISTERED CIVIL ENGINEER				
				
PLANS APPROVAL DATE				
The State of California is the authority on the validity of this seal. It is the responsibility of the engineer to maintain the seal in good standing.				
California Seal is valid until 7/1/2011. If you do not wish to renew your seal, please contact the State Board of Professional Engineers.				




PLAN VIEW

**DRAINAGE SYSTEM No. 3**

NOTES

1. SEE SHEET D-4 FOR SECTION B-B AND SECTION C-C.
2. SEE SECTION C-C FOR REINFORCEMENT DETAILS AND CONCRETE STRENGTH INFORMATION.



SECTION A-A

**DRAINAGE SYSTEM No. 3**

ALL DIMENSIONS ARE IN METERS UNLESS OTHERWISE SHOWN

**DRAINAGE DETAILS**

SCALE 11:50

Attachment 4, sheet 1

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION		PROJECT ENGINEER		CHARLES CHULAPALA		CHECKED BY		DATE	
DESIGNED BY		DATE		REVISOR		DATE		DATE	

FOR REDUCED PLANS ORIGINAL SCALE 1:12 MILLIMETERS

USE INK - NO PENCIL

CU 07508

EA 407001

NO

40

80

120

160

200

240

280

320

360

400

440

480

520

560

600

640

680

720

760

800

840

880

920

960

1000

1040

1080

1120

1160

1200

1240

1280

1320

1360

1400

1440

1480

1520

1560

1600

1640

1680

1720

1760

1800

1840

1880

1920

1960

2000

2040

2080

2120

2160

2200

2240

2280

2320

2360

2400

2440

2480

2520

2560

2600

2640

2680

2720

2760

2800

2840

2880

2920

2960

3000

3040

3080

3120

3160

3200

3240

3280

3320

3360

3400

3440

3480

3520

3560

3600

3640

3680

3720

3760

3800

3840

3880

3920

3960

4000

4040

4080

4120

4160

4200

4240

4280

4320

4360

4400

4440

4480

4520

4560

4600

4640

4680

4720

4760

4800

4840

4880

4920

4960

5000

5040

5080

5120

5160

5200

5240

5280

5320

5360

5400

5440

5480

5520

5560

5600

5640

5680

5720

5760

5800

5840

5880

5920

5960

6000

6040

6080

6120

6160

6200

6240

6280

6320

6360

6400

6440

6480

6520

6560

6600

6640

6680

6720

6760

6800

6840

6880

6920

6960

7000

7040

7080

7120

7160

7200

7240

7280

7320

7360

7400

7440

7480

7520

7560

7600

7640

7680

7720

7760

7800

7840

7880

7920

7960

8000

8040

8080

8120

8160

8200

8240

8280

8320

8360

8400

8440

8480

8520

8560

8600

8640

8680

8720

8760

8800

8840

8880

8920

8960

9000

9040

9080

9120

9160

9200

9240

9280

9320

9360

9400

9440

9480

9520

9560

9600

9640

9680

9720

9760

9800

9840

9880

9920

9960

10000

10040

10080

10120

10160

10200

10240

10280

10320

10360

10400

10440

10480

10520

10560

10600

PROJECT NO.	07	COUNTY	LA	ROUTE	39	TOTAL SHEETS	36	THIS SHEET	14
DATE	07/14/00	DESIGNED BY	CHARLES CHILIPALA	CHECKED BY	CHARLES CHILIPALA	DATE	07/14/00	REVIEWED BY	
PROJECT ENGINEER	CHARLES CHILIPALA	REGISTERED CIVIL ENGINEER	NO. 47149	EXPIRATION DATE	07/14/03	PLANS APPROVAL DATE	07/14/00	APPROVED BY	



California State Seal and Seal of the State Engineer, State of California

FOR REDUCED PLANS ONLY  
SCALE: 1/8" = 1'-0"

SECTION B-B

SECTION C-C

CONCRETE STRENGTHS

STRUCTURAL CONCRETE (INVERT PAVING) (45 MPa at 28 Days)

STRUCTURAL CONCRETE (INVERT PAVING) (35 MPa at 28 Days)

SCALE 1:20

DRAINAGE UNIT No. 3



DRAINAGE DETAILS

Attachment 4, Sheet 2

CU 07608

EA 4GT001

00-00-00-00





STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION

PROJECT ENGINEER

DESIGNED BY

CHECKED BY

DATE



## MATERIAL SITE PLAN

**SCALE 1:500**

## ATTACHMENT 5

EA 4G7001

CU 07608

USER NAME -> SUPER  
 DON FILE -> ONEQUEST

FOR REDUCED PLANS ORIGINAL  
SCALE IS IN MILLIMETERS

1

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION  
Highways MAINTENANCE DESIGN

PROJECT ENGINEER

DESIGNED BY	DATE
CHECKED BY	DATE

REVISOR BY	DATE REVISED
------------	--------------

DATE REVISED

## ***Appendix B List of Acronyms***

## **List of Acronyms**

ADL	Aerially deposited lead
ADT	Average Daily Traffic
CALTRANS	California Department of Transportation
CDFG	California Department of Fish and Game
CEQA	California Environmental Quality Act
CNDDDB	California Natural Diversity Database
FT	Feet
FHWA	Federal Highways Administration
EA	Expenditure Authorization
HCP	Habitat Conservation Plan
HPSR	Historical Property Survey Report
IS	Initial Study
M	Meter
METS	Materials Engineering and Testing Services
MSL	Mean Sea Level
NCCP	Natural Community Conservation Plan
PM	Post Mile
RE	Resident Engineer
RWQCB	Regional Water Quality Control Board
SCH	State Clearinghouse
SWPPP	Storm Water Pollution Prevention Plan
U.S.	United States
USACOE	United States Army Corps of Engineers
USDAFS	United States Department of Agriculture and Forest Service
USFWS	United States Fish and Wildlife Service
WPCP	Water Pollution Control Plan

## ***Appendix C Summary of Measures to Minimize Harm***

**SUMMARY CHART OF MEASURES TO MINIMIZE HARM  
BROWN'S GULCH CULVERT REHABILITATION PROJECT (EA: 4G7000)**

<b>Environmental Concern</b>	<b>Mitigation Measure</b>	<b>Timing of Mitigation</b>	<b>Unit Responsible for Mitigation Monitoring</b>
<b>Visual Aesthetics</b>	The integrity of the visual aesthetics in the area would be minimized by the proposed hydro seeding of the proposed access ramp after construction is completed	Construction	Contractor/Resident Engineer (RE), Landscaping, and Environmental
<b>Air Quality 1</b>	All clearing, grubbing, grading, earth moving, or excavation activities shall cease during periods of high winds to prevent excessive amounts of fugitive dust.	Construction	RE
<b>Air Quality 2</b>	All trucks that haul excavated material off site shall comply with the State Vehicles Code Section 23114.	Construction	RE
<b>Air Quality 3</b>	All active portions off site and unpaved on-site roads shall be periodically watered with an environmentally safe dust suppressant to prevent excessive amounts of dust.	Construction	RE
<b>Air Quality 4</b>	Areas disturbed by clearing, grading earth moving, or excavation operations shall be minimized to prevent excessive amounts of fugitive dust.	Design/Construction	Environmental/RE
<b>Air Quality 5</b>	On-site vehicle speed shall not exceed 15 miles per hour.	Construction	RE
<b>Air Quality 6</b>	Construction equipment engines shall be maintained in good condition and in proper tune as per manufacturers' specifications.	Construction	RE

<b>Environmental Concern</b>	<b>Mitigation Measure</b>	<b>Timing of Mitigation</b>	<b>Unit Responsible for Mitigation Monitoring</b>
<b>Biological Resources 1</b> -----Permits	<p>The following permits will be obtained through coordination with the appropriate agency:</p> <ul style="list-style-type: none"> <li>▪ 1601 Streambed Alteration Agreement (California Department of Fish and Game)</li> <li>▪ 404 Permit (U.S. Army Corps of Engineers)</li> <li>▪ 401 Permit (California Regional Water Quality Control Board)</li> </ul> <p>All provision required by these permits will be incorporated into the project specifications, and a mutually acceptable mitigation plan will be prepared.</p>	Pre-construction	Environmental
<b>Biological Resources 2</b> -----Vegetation	Removal of exotics will be conducted within the project area.	Pre-and post-construction	Environmental
<b>Biological Resources 3</b> -----Vegetation	Vegetation shall be cleared and grubbed only within the excavation and embankment slope lines. Adjacent canyon/hillsides and existing vegetation outside the areas to be cleared, grubbed, borrowed, filled, and graded shall be protected from damage resulting from the Contractor's operations with the use of fencing. This will be applicable to the burrow sites and the culvert rehabilitation site.	Pre-Construction	Contractor, RE, Environmental Planning



<b>Environmental Concern</b>	<b>Mitigation Measure</b>	<b>Timing of Mitigation</b>	<b>Unit Responsible for Mitigation Monitoring</b>
<b>Biological Resources 4</b> -----Vegetation	There exists a mature Live Oak tree at borrow site #2. If grade change is necessary in the area, it shall take place only on the outside of the tree's drip-line. The oak shall also be fenced 2 feet beyond the drip line prior to any grade lowering so as not to be disturbed or damaged during these activities. Lastly, all these activities shall also be coordinated with both the Division of Environmental Planning and the Office of Landscape Architecture.	Pre-Construction	Contractor/RE, Office of Landscape Architecture and Environmental Planning
<b>Biological Resources 5</b> -----Vegetation	The top 6" upper crust/top soil of fill from the borrow sites shall be skimmed and disposed of in order to lessen the possibility of transporting weeds and non-native plant seeds to the Culvert Rehabilitation site, where native vegetation will be hydro-seeded.	Construction	Contractor/RE
<b>Biological Resources 6</b> -----Vegetation	If plant species outside the permanent impact area must be cleared, it will be cut above ground so as to allow for resprouting.	Construction	Contractor/RE
<b>Biological Resources 7</b> -----Vegetation	All native trees removed shall be mitigated 10:1 in kind and on-site.	Construction	Contractor/RE and Environmental Planning

<b>Environmental Concern</b>	<b>Mitigation Measure</b>	<b>Timing of Mitigation</b>	<b>Unit Responsible for Mitigation Monitoring</b>
<b>Biological Resources 8</b> -----Nesting Birds	<p>Since construction is scheduled to take place during the bird-nesting season (<b>March 1 - September 1</b>), all affected vegetation shall be removed prior to avoid impacting the nesting birds. Since this will necessitate working during the rainy season, provisions need to be made so as not to impact water quality during these activities (this will be the only work allowed during the rainy season). Thus, clearing and grubbing shall only be conducted during dry weather and when rain is not forecasted for that day, and when there is no water flowing in the intermittent stream. Also, please see water quality measures.</p>	Construction	Contractor/RE
<b>Biological Resources 9</b> -----Nesting Birds	<p>A district biologist will survey the appropriate areas for nesting birds a minimum of once every ten days. The surveys will concentrate on areas where there are adjacent trees, where nesting birds are potentially located. If nesting birds are found, the area will be flagged and a buffer zone will be established where work would be prohibited.</p>	Construction	Contractor/RE and Environmental Planning/Biologist
<b>Biological Resources 10</b> -----Construction	<p>The perimeter of the construction area will be fenced and flagged to prevent damage to the adjacent area.</p>	Pre-construction	RE
<b>Biological Resources 11</b> -----Construction	<p>To avoid impacts to sensitive wildlife species, construction areas will not be lighted during non-daylight hours.</p>	Construction	RE

<b>Environmental Concern</b>	<b>Mitigation Measure</b>	<b>Timing of Mitigation</b>	<b>Unit Responsible for Mitigation Monitoring</b>
<b>Biological Resources 12</b> -----Construction	If previously unknown sensitive species or other biological resources are encountered after construction has commenced, all work shall halt in the vicinity until consultation has taken place with the appropriate resource agency.	Construction	RE
<b>Biological Resources 13</b> -----Construction	To avoid impacts to sensitive wildlife species, construction activities will be limited to daylight hours.	Construction	RE
<b>Biological Resources 14</b> -----Construction	Construction storage will be in a designated non-sensitive area. Construction equipment will be stored outside of the channel (defined as top of slope to top of slope), away from the stream banks. No equipment maintenance will be performed in the streambed.	Construction	RE
<b>Biological Resources 15</b> -----Construction	Contractor maintenance equipment and repair items are to be stored in an area that is currently paved, and that will not impair the road in any way or impact the biological diversity of the area.	Construction	Contractor/RE
<b>Biological Resources 16</b> -----Construction	Contractor and maintenance personnel shall look under mechanical equipment (before moving) for animals (reptiles, amphibians, and mammals) that may use the equipment for cover.	Construction	Contractor/RE

<b>Environmental Concern</b>	<b>Mitigation Measure</b>	<b>Timing of Mitigation</b>	<b>Unit Responsible for Mitigation Monitoring</b>
<b>Cultural Resources 1</b>	It is Caltrans policy that if cultural materials appear during construction, work will stop in the immediate area. The District 7 Cultural Resource staff will be notified upon such discovery and appropriate measures will be performed to mitigate impacts to the resource. Work may only resume with approval from the Caltrans archaeologist.	Construction	RE
<b>Geology and Soils 1</b>	Embankment construction should conform to Section 19 of the Standard Specifications.	Design/Construction	RE/Contractor
<b>Geology and Soils 2</b>	The use of geosynthetic reinforcement is recommended	Design	Design
<b>Hazards 1</b>	A fire prevention and control program will be established that limits activity in and adjacent to flammable vegetation. A full water truck should be available should a fire occur within the project area.	Design	Design/Environmental
<b>Hazards 2</b>	Should excavation reveal unknown potentially hazardous materials, Caltrans policy would require work to halt in the immediate vicinity until the area in question could be investigated and proper mitigation could be proposed.	Construction	RE

<b>Environmental Concern</b>	<b>Mitigation Measure</b>	<b>Timing of Mitigation</b>	<b>Unit Responsible for Mitigation Monitoring</b>
<b>Water Quality 1</b>	<p>The following permits are required as part of the SWPPP and WPCP for this project:</p> <ul style="list-style-type: none"> <li>• Regional Water quality Control Board 401 Permit</li> <li>• U.S. Army Corps of Engineers 404 Permit</li> <li>• California Department of Fish and Game 1601 Streambed Alteration Agreement</li> <li>• NPDES Storm Water Pollution Prevention Plan</li> </ul>	Pre-Construction	Design and Environmental
<b>Water Quality 2</b>	The contractor shall provide a Storm Water Pollution Prevention Plan (SWPPP) and erosion control plan. The plans must be approved by the Resident Engineer (RE) and submitted for approval to the RWQCB.	Pre-construction	Environmental/RE
<b>Water Quality 3</b>	Best storm water pollution control management practices will be implemented to protect the Construction Zone from local flooding and to prevent contaminated runoff or prevent excessive silt and other erosion from entering the Culvert or any other drainage. Sandbag barriers, check dams, sediment traps, and other erosion control measures will be provided	Pre – Construction and Construction	Contractor/RE
<b>Water Quality 4</b>	All work will be conducted outside of the rain season (Oct 1 <sup>st</sup> – March 30 <sup>th</sup> ), except for the cutting of the above mentioned potential nesting vegetation which will be done prior to February 15 <sup>th</sup> .	Construction	Contractor/RE

<b>Environmental Concern</b>	<b>Mitigation Measure</b>	<b>Timing of Mitigation</b>	<b>Unit Responsible for Mitigation Monitoring</b>
<b>Water Quality 5</b>	Raw cement/concrete or washings thereof, asphalt, paint, oil/other petroleum products, or any other substances which could be hazardous to aquatic life, resulting from project related activities, shall be prevented from contaminating the soil and/or entering the culvert or any drainages.	Construction	Contractor/RE
<b>Water Quality 6</b>	Construction will be limited to low-flow periods to minimize impacts to water quality.	Construction	Environmental/RE
<b>Water Quality 7</b>	Should it rain during vegetation grubbing and removal or construction, work shall be halted until flows subside.	Construction	RE
<b>Water Quality 8</b>	No foreign material (concrete, oil, fuel, excavated material) will be allowed to enter the active streambed or culvert. Best Management Practices will be implemented. This could include sandbag barriers, check dams, sediment traps, and other erosion control measures.	Construction	RE
<b>Water Quality 9</b>	Standard erosion control will be provided on new slopes according to State and Federal water quality discharge requirements.	Construction	Contractor Landscaping/Environmental
<b>Noise 1</b>	The contractor shall comply with all local sound control and noise level rules, regulations and ordinances that apply to any work performed pursuant to the contract.	Construction	RE
<b>Noise 2</b>	Each internal combustion engine, used for any purpose on the job or related to the job, shall be equipped with a muffler of a type recommended by the manufacturer. No internal combustion engine shall be operated on the project without the muffler.	Construction	Contractor/RE



<b>Environmental Concern</b>	<b>Mitigation Measure</b>	<b>Timing of Mitigation</b>	<b>Unit Responsible for Mitigation Monitoring</b>
<b>Construction</b>	Maintenance and Construction equipment shall be checked and maintained daily by contractor so as to prevent leaks or other potential contamination problems.	Construction	Contractor/RE
<b>Construction</b>	At the end of the day when operations are complete, any excess materials, debris or trash shall be removed from the work area and properly disposed of by contractor. All personnel working within the project area will follow all litter and pollution laws.	Construction	Contractor/RE
<b>Construction</b>	Daily removal of dirt spilled on to paved roads	Construction	Contractor/RE
<b>Construction</b>	Contractor shall phase grading to minimize the area of disturbed soils	Construction	Contractor/RE
<b>Construction</b>	Contractor shall phase construction activities to minimize daily emissions	Construction	Contractor/RE
<b>Construction</b>	Contractor shall properly maintain construction vehicles to maximize efficiency and minimize emissions	Construction	Contractor/RE
<b>Construction</b> -----Dust	Contractor shall stabilize construction roads and dirt piles with water twice daily	Construction	Contractor/RE
<b>Construction</b> -----Dust	Contractor shall limit speeds on unpaved construction roads to 15mph	Construction	Contractor/RE

<b>Environmental Concern</b>	<b>Mitigation Measure</b>	<b>Timing of Mitigation</b>	<b>Unit Responsible for Mitigation Monitoring</b>
<b>Construction</b> -----Dust	Contractor shall cease grading and excavation activities when wind speeds exceed 25 miles per hour and during extreme air pollution episodes	Construction	Contractor/RE
<b>Construction</b> -----Dust	Contractor shall require covering of all haul trucks	Construction	Contractor/RE
<b>Transportation/Traffic</b>	Construction will take place only on weekdays in order to minimize the possibility of traffic increases during construction	Construction	Contractor/RE



## ***Appendix D Scoping Notice***

**DEPARTMENT OF TRANSPORTATION**

Division of Environmental Planning

120 SPRING STREET

LOS ANGELES, CA 90012

PHONE (213) 897-0703

FAX (213) 897-0685

*Flex your power!  
Be energy efficient!*

February 11, 2002

File: 07-LA 39 (PM 22.46)

Culvert Rehabilitation

EA: 4G7000

**Notice of Scoping/Initiation of Studies**

Caltrans is formally initiating studies for a Culvert Rehabilitation project on State Route 39 in Los Angeles County. The project proposes to rebuild an existing culvert bottom described as a 2.7m Diameter Horseshoe Shaped Culvert, fill in gullies below existing channel invert with rock, create a permanent access ramp, and restore an eroded fill slope. Clearing and grubbing of vegetation as well as grading will be required. The project is located at Brown's Gulch, a blue line stream that is within the United States Angeles National Forest.

Preliminary environmental resource studies and agency coordination have indicated that the resulting environmental document will be an Initial Study/Environmental Assessment that is expected to lead to a Focused Negative Declaration/Finding of No Significant Impact (ND/FONSI). The focus of this document will be on the biological resources that are present in the project area.

In order to ensure that all pertinent factors are considered, Caltrans will work cooperatively with other agencies and their staffs, community members, and community groups throughout this study. Comments or suggestions that you may have concerning potential social, economic, and environmental impacts under this proposal are welcome.

If requested, a public hearing will be held to discuss the specific parameters of this project once adequate studies have been completed. Advance notification of the public hearing time and location will be well publicized.

If you have any questions regarding this proposed project please send your written comments by March 20, 2002 to:

Ronald J. Kosinski, Deputy District Director  
Division of Environmental Planning (07-LA 39 P.M. 22.46 Culvert Rehabilitation)  
California Department of Transportation, District 7  
120 S. Spring Street (MS 16A)  
Los Angeles, CA 90012

If you have any questions or need additional information please contact Ronald Kosinski at (213) 897-0703 (email: Ron\_Kosinski@dot.ca.gov) or Amy Pettler at (213) 897-8081 email: Amy\_Pettler@dot.ca.gov).

Thank you for your interest in this transportation maintenance study.



Sincerely,

RONALD J. KOSINSKI

Deputy District Director, Division of Environmental Planning  
California Department of Transportation

# Project Location Map

## State Route 39 Brown's Gulch Culvert Rehabilitation



## ***Appendix E Scoping Comments***



United States  
Department of  
Agriculture

Forest  
Service

San Gabriel River  
Ranger District

110 N. Wabash Ave.  
Glendora, CA 91741  
626-335-1251 Voice  
626-574-5209 TTY

File Code: 7400

Date: February 25, 2002

Ronald Kosinski  
Division of Environmental Planning  
Caltrans  
120 S. Spring Street (MS 16A)  
Los Angeles, CA 90012

Dear Mr. Kosinski:

I am writing in response to your letter dated February 11, 2002, referenced as File: 07-LA 39, (PM 22.46), State Route 39 Culvert Rehabilitation, EA: 4G7000.

I would like your analysis to consider the visual impacts of creating a permanent access ramp off of the highway, especially if the access ramp is to be located on the east side of SR 39. In addition, any downstream sedimentation created during ramp construction will need to be considered.

I will need to review the archaeological and biological reports prepared by your specialists. Once these are completed, please forward them to my office for review. We would also like to review the Focused Negative Declaration/Finding of No Significant Impact (ND/FONSI).

Should you have questions, please contact Karen Fortus at (626) 335-1251 extension 249.

Sincerely,


*Marty Dumpis*

MARTY DUMPIS

District Ranger



SOUTHERN CALIFORNIA



**ASSOCIATION of  
GOVERNMENTS**

**Main Office**

818 West Seventh Street

12th Floor

Los Angeles, California

90017-3435

t (213) 236-1800

f (213) 236-1825

[www.scag.ca.gov](http://www.scag.ca.gov)

**Officers:** President: Supervisor Jon Mikels, County of San Bernardino • First Vice President: Councilmember Hal Bernson, Los Angeles • Second Vice President: Mayor Pro Tem Bev Perry, Brea • Immediate Past President: Mayor Ron Bates, Los Alamitos

**Imperial County:** Hank Kulper, Imperial County

**Los Angeles County:** Yvonne Brathwaite Burke, Los Angeles County • Zev Yaroslavsky, Los Angeles County • Harry Baldwin, San Gabriel • Bruce Barrows, Cerritos • George Bass, Bell • Hal Bernson, Los Angeles • Robert Brunsch, Rosemead • Gene Daniels, Paramount • Jo Anne Darcy, Santa Clarita • Ruth Galanter, Los Angeles • Eric Garcetti, Los Angeles • Ray Grahinski, Long Beach • James Hahn, Los Angeles • Janice Hahn, Los Angeles • Dee Hardison, Torrance • Nate Holden, Los Angeles • Sandra Jacobs, El Segundo • Lawrence Kirkley, Inglewood • Bonnie Lowenthal, Long Beach • Keith McCarthy, Downey • Cindy Miskowski, Los Angeles • Stacey Murphy, Burbank • Pam O'Connor, Santa Monica • Nick Pacheco, Los Angeles • Alex Padilla, Los Angeles • Jan Perry, Los Angeles • Beatrice Proo, Pico Rivera • Mark Ridley-Thomas, Los Angeles • Ed Reyes, Los Angeles • Karen Rosenthal, Claremont • Dick Stanford, Azusa • Tom Sykes, Walnut • Paul Talbot, Alhambra • Sidney Tyler, Jr., Pasadena • Joel Wachs, Los Angeles • Dennis Washburn, Calabasas • Jack Weiss, Los Angeles • Dennis P. Zima, Los Angeles

**Orange County:** Charles Smith, Orange County • Ron Bates, Los Alamitos • Ralph Bauer, Huntington Beach • Art Brown, Buena Park • Lou Bone, Tustin • Elizabeth Cowan, Costa Mesa • Cathryn DeYoung, Laguna Niguel • Richard Dison, Lake Forest • Alta Duke, La Palma • Shirley McCracken, Anaheim • Bev Perry, Brea • Tod Ridgeway, Newport Beach

**Riverside County:** Bob Buster, Riverside County • Ron Loveridge, Riverside • Greg Pettis, Cathedral City • Ron Roberts, Temecula • Jan Rudman, Corona • Charles White, Moreno Valley

**San Bernardino County:** Jon Mikels, San Bernardino County • Bill Alexander, Rancho Cucamonga • David Ehleman, Fontana • Lee Ann Garcia, Grand Terrace • Bob Hunter, Victorville • Gwenn Norton-Perry, Chino Hills • Judith Valles, San Bernardino

**Ventura County:** Judy Mikels, Ventura County • Glen Bocerra, Simi Valley • Donna De Paola, San Buenaventura • Toni Young, Port Hueneme

**Riverside County Transportation Commission:** Robin Lowe, Hemet

**Ventura County Transportation Commission:** Bill Davis, Simi Valley

March 12, 2002

Mr. Ronald J. Kosinski, Deputy District Director  
Division of Environmental Planning (07-LA 39 P.M. 22.46 Culver Rehabilitation)  
California Department of Transportation, District 7  
120 S. Spring Street (MS 16A)  
Los Angeles, CA 90012

**RE: SCAG Clearinghouse No. I 20020110 Culvert Rehabilitation**

Dear Mr. Kosinski:

Thank you for submitting the **Culvert Rehabilitation** to SCAG for review and comment. As areawide clearinghouse for regionally significant projects, SCAG reviews the consistency of local plans, projects and programs with regional plans. This activity is based on SCAG's responsibilities as a regional planning organization pursuant to state and federal laws and regulations. Guidance provided by these reviews is intended to assist local agencies and project sponsors to take actions that contribute to the attainment of regional goals and policies.

We have reviewed the **Culvert Rehabilitation**, and have determined that the proposed Project is not regionally significant per SCAG Intergovernmental Review (IGR) Criteria and California Environmental Quality Act (CEQA) Guidelines (Section 15206). Therefore, the proposed Project does not warrant comments at this time. Should there be a change in the scope of the proposed Project, we would appreciate the opportunity to review and comment at that time.

A description of the proposed Project was published in SCAG's **March 1, 2002** Intergovernmental Review Clearinghouse Report for public review and comment.

The project title and SCAG Clearinghouse number should be used in all correspondence with SCAG concerning this Project. Correspondence should be sent to the attention of the Clearinghouse Coordinator. If you have any questions, please contact me at (213) 236-1867. Thank you.

Sincerely,

  
JEFFREY M. SMITH, AICP  
Senior Planner,  
Intergovernmental Review

FEB. 19, 2002

TO: RONALD J. KOSINSKI, DEPUTY DISTRICT DIRECTOR,  
CALTRANS.

REGARDING CULVERT REHABILITATION (07-LA 39  
PM, 22.46)

IF NO ACTION IS TAKEN TO REHABILITATE THIS  
CULVERT, "... FILL IN GULLIES EXISTING CHANNEL  
INVERT WITH ROCK, CREATE A PERMANENT ACCESS  
RAMP AND RESTORE AN ERODED FILL SLOPE, "  
THEN DOING NOTHING WILL CAUSE THE REASONS  
FOR PERFORMING THE ABOVE CONDITIONS TO GET  
WORST. THUS LEAVING AN EVEN LARGER  
REBUILDING ~~B~~ JOB BECAUSE OF AGING AND  
EROSION, THUS CAUSING MORE SIGNIFICANT  
DISTURBANCE, THUS DESTROYING MORE ENDANGERED  
SPECIES. HIGHWAY 39 IS USED BY THOUSANDS  
AND THOUSANDS OF FOREST USERS EACH YEAR,  
IT MUST BE MAINTAINED TO KEEP IT OPEN AND  
TO KEEP IT SAFE. WHEN IT HAS TO BE REPAIRED,  
IT HAS TO BE REPAIRED.

I FEEL THAT THIS IS AN IMPORTANT AND  
ESSENTIAL PROJECT THAT HAS TO BE DONE

SINCERELY

CHUCK UCKER

1453 S. RIMHURST AVE.

GLENORA, CA.

91740



## DEPARTMENT OF TRANSPORTATION

Division of Environmental Planning

120 SPRING STREET

LOS ANGELES, CA 90012

PHONE (213) 897-0703

FAX (213) 897-0685



*Flex your power!  
Be energy efficient!*

FILED RECEIVED

FEB 21 2002

FEB 14 P2:30

February 11, 2002

CONNOR B. MCCORMACK, COUNTY CLERK

File: 07-LA 39 (PM 22.46)

Culvert Rehabilitation  
EA: 407000

## Notice of Scoping/Initiation of Studies

Caltrans is formally initiating studies for a Culvert Rehabilitation project on State Route 39 in Los Angeles County. The project proposes to rebuild an existing culvert bottom described as a 2.7m Diameter Horseshoe Shaped Culvert, fill in gullies below existing channel invert with rock, create a permanent access ramp, and restore an eroded fill slope. Clearing and grubbing of vegetation as well as grading will be required. The project is located at Brown's Gulch, a blue line stream that is within the United States Angeles National Forest.

Preliminary environmental resource studies and agency coordination have indicated that the resulting environmental document will be an Initial Study/Environmental Assessment that is expected to lead to a Focused Negative Declaration/Finding of No Significant Impact (ND/FONSI). The focus of this document will be on the biological resources that are present in the project area.

In order to ensure that all pertinent factors are considered, Caltrans will work cooperatively with other agencies and their staffs, community members, and community groups throughout this study. Comments or suggestions that you may have concerning potential social, economic, and environmental impacts under this proposal are welcome.

If requested, a public hearing will be held to discuss the specific parameters of this project once adequate studies have been completed. Advance notification of the public hearing time and location will be well publicized.

If you have any questions regarding this proposed project please send your written comments by March 20, 2002 to:

Ronald J. Kosinski, Deputy District Director  
Division of Environmental Planning (07-LA 39 P.M. 22.46 Culvert Rehabilitation)  
California Department of Transportation, District 7  
120 S. Spring Street (MS 16A)  
Los Angeles, CA 90012

If you have any questions or need additional information please contact Ronald Kosinski at (213) 897-0703 (email: Ron\_Kosinski@dot.ca.gov) or Amy Pettler at (213) 897-8081 email: Amy\_Pettler@dot.ca.gov).

Thank you for your interest in this transportation maintenance study.

Sincerely,

*Ronald Kosinski*  
RONALD J. KOSINSKI

Deputy District Director, Division of Environmental Planning  
California Department of Transportation

THIS NOTICE WAS POSTED  
ON FEB 21 2002

UNTIL MAR 25 2002

REGISTRAR-RECORDER/COUNTY CLERK



## ***Appendix F Mailing List***

## **Circulation Distribution List**

The Honorable Carol Liu  
Assemblymember, District 44  
215 North Marengo Avenue, Suite 115  
Pasadena, CA 91101

The Honorable David Dreier  
U.S. Congressman, District 26  
2220 East Route 66, Suite 225  
Glendora, CA 91740

The Honorable Dennis Lee Mountjoy  
Assemblymember, District 59  
135 West Lemon Ave., Suite A  
Monrovia, CA 91016

United States Department of Agriculture Forest Service  
San Gabriel River Ranger District  
110 N. Wabash Ave.  
Glendora, CA 91471

Southern California Association of Governments  
818 West Seventh St., 12<sup>th</sup> Floor  
Los Angeles, CA 90017-3435

California Department of Fish and Game  
South Coast Region  
Attention: Trudy Ingram  
4949 Viewridge Ave.  
San Diego, CA 92123

California Regional Water Quality Control Board  
320 W. 4<sup>th</sup> Street, Suite 200  
Los Angeles, CA 90013

Mr. Jonathan Synder  
U.S. Fish and Wildlife Service  
Carlsbad Field Office  
2730 Loker Avenue West  
Carlsbad, CA 92008

Azusa Chamber of Commerce  
240 West Foothill Blvd.  
Azusa, CA 91702

Jody Cook  
USDA – Forest Service Forest Supervisor  
Angeles National Forest  
701 North Santa Anita Avenue  
Arcadia, CA 91006

Mr. Marty Dumpis  
San Gabriel River Ranger District  
District Ranger  
110 North Wabash Avenue  
Glendora, CA 91740

Mr. Mike McIntyre  
Angeles National Forest  
Forest Archaeologist  
701 North Santa Anita Avenue  
Arcadia, CA 91006

Headquarters Environmental Program  
1120 N. Street, MS – 27  
PO Box 942874  
Sacramento, CA 94274-0001

State Water Resources Board  
P.O. Box 944212  
Sacramento, CA 94244-2130

## Circulation Distribution List

State Clearinghouse  
Office of Planning and Research  
P.O. Box 3044  
Sacramento, CA 94233-3044

County of Los Angeles  
Registrar-Recorder/County Clerk  
Attn: Conny B. McCormack  
P.O. Box 1024  
Norwalk, CA 90651

California State Lands Commission  
Attn: Robert C. Hight  
100 Howe Ave., Suite 100 South  
Sacramento, CA 95825-8202

California Dep. Of Forestry and Fire Protection  
P.O. Box 94246  
Sacramento, CA 94244-2460

Los Angeles Department of Water and Power  
Attn: Ms. Jodean Giese  
11 North Hope St. Room 1121  
Los Angeles, CA 90012

County of Los Angeles  
Fire Department  
Attn: David R. Leininger  
1320 North Eastern Avenue  
Los Angeles, CA 90063-3294

County of Los Angeles Watershed Management Division  
Attn: Suk Chong  
900 South Fremont Ave., 11<sup>th</sup> Floor  
Alhambra, CA 91803-1331

Fire Departments  
5980 Elm Street  
Wrightwood, CA 92397

Bill Brown  
Angeles National Forest  
Forest Biologist  
701 N. Santa Anita Ave.  
Arcadia, CA 91006

John R. Zeigler, Senior Transportation Engineer  
Automobile Club of Southern California  
Public Affairs, A-131  
3333 Fairview Road  
Costa Mesa, CA 92626

Chief E.W. Gomez  
California Highway Patrol  
411 N. Central Avenue, Suite 410  
Glendale, CA 91203-2020

Mr. Greg Newhouse  
California Energy Commission  
1516 Ninth Street  
Sacramento, CA 95814

Chair Jo Thompson  
Public Works  
1327 Foothill Blvd.  
La Canada Flintridge, CA 91011

Southern California Association of Governments  
818 West Seventh Street, 12<sup>th</sup> Floor  
Los Angeles, CA 90017-3435

## **Circulation Distribution List**

Mr. P. Michael Freeman, Fire Chief  
L.A. County Fire Department  
1320 North Eastern Ave.  
Los Angeles, CA 90063

California Native Plant Society  
1722 J Street  
Sacramento, CA 95814

Environmental Clearing Officer Dept. of Housing and Urban  
Development  
450 Golden Gate Avenue  
P.O. Box 36003  
San Francisco, CA 94102

State Clearinghouse  
1400 Tenth Street  
Sacramento, CA 95814

Mr. James Hartl, Planning Director  
L.A. County Dept. of Regional Planning  
Hall of Records, 13<sup>th</sup> Floor  
320 West Temple Street  
Los Angeles, CA 90012

Mr. Barry R. Wallerstein, Executive Officer  
South Coast Air Quality Management District  
21865 E. Copley Drive  
Diamond Bar, CA 91765

Mr. Hans Kreutzberg  
Office of Historic Preservation  
Department of Parks and Recreation  
P.O. Box 942896  
Sacramento, CA 94296-0001

Forest Preservation Society  
4023 Chaney Trail  
Altadena, CA 91001

# Scoping Mailing List

## Elected Officials

The Honorable Carol Liu  
Assemblymember, District 57  
215 North Marengo Avenue  
Pasadena, CA 91101

The Honorable David Dreier  
U.S. Congressmember, District 28  
112 North 2<sup>nd</sup> Avenue  
Covina, CA 91723

The Honorable Dennis Lee Mountjoy  
Assemblymember, District 59  
500 N. 1<sup>st</sup> Ave.  
Arcadia, CA 91006

## Agencies

United States Department of Agriculture  
Forest Service  
San Gabriel River Ranger District  
110 N. Wabash Ave.  
Glendora, CA 91471

Southern California Association of Governments  
818 West Seventh St., 12<sup>th</sup> Floor  
Los Angeles, CA 90017-3435

California Department of Fish and Game  
South Coast Region  
Attention: Trudy Ingram  
4949 Viewridge Ave.  
San Diego, CA 92123

California Regional Water Quality Control Board  
320 West 4<sup>th</sup> Street, Suite 200  
Los Angeles, CA 90013

Mr. Jonathan Synder  
U.S. Fish and Wildlife Service  
Carlsbad Field Office  
2730 Loker Avenue West  
Carlsbad, CA 92008

Azusa Chamber of Commerce  
240 West Foothill Blvd.  
Azusa, CA 91702

Jody Cook  
USDA – Forest Service Forest Supervisor  
Angeles National Forest  
701 North Santa Anita Avenue  
Arcadia, CA 91006

Mr. Marty Dumpis  
San Gabriel River Ranger District  
District Ranger  
110 North Wabash Avenue  
Glendora, CA 91740

Mr. Mike McIntyre  
Angeles National Forest  
Forest Archaeologist  
701 North Santa Anita Avenue  
Arcadia, CA 91006

Headquarters Environmental Program  
1120 N Street, MS - 27  
PO Box 942874  
Sacramento, CA 94274-0001

State Water Resources Board  
P.O. Box 944212  
Sacramento, CA 94244-2130

State Clearinghouse  
Office of Planning and Research P.O. Box 3044  
Sacramento, CA 94244-3044

County of Los Angeles  
Registrar-Recorder/County Clerk  
P.O. Box 53592  
Los Angeles, CA 90053-1331

California State Lands Commission  
Attn: Robert C. Hight  
100 Howe Ave., Suite 100 South  
Sacramento, CA 95825-8202

California Dep. of Forestry and Fire Protection  
P.O. Box 944246  
Sacramento CA 94244-2460

County of Los Angeles  
Fire Department  
Attn: David R. Leininger  
1320 North Eastern Avenue  
Los Angeles, CA 900633294

Fire Departments  
5980 Elm Street  
Wrightwood, CA 92397

Los Angeles Department of Water and Power  
Attn: Ms. Jodean Giese  
111 North Hope St., Room 1121  
Los Angeles, CA 90012

County of Los Angeles  
Watershed Management Division  
Attn: Suk Chong  
900 South Fremont Avenue, 11<sup>th</sup> Floor  
Alhambra, CA 91803-1331

Bill Brown  
Angeles National Forest  
Forest Biologist  
701 North Santa Anita Avenue  
Arcadia, CA 91006

## General Public

WRIGHTWOOD PROPERTY OWNERS  
STANLEY MURPHY  
P.O. BOX 2357  
WRIGHTWOOD, CA 92397

MIDDLE RANCH  
FRITZ TEGATZ  
11700 N. LITTLE TUJUNGA CANYON RD  
LAKEVIEW TERRACE, CA 91342

FISHERIES RESOURCE VOL CORPS  
BILL REEVES  
6815 NEVADA CT.  
ALTA LOMA, CA 91701

SHIA  
RONALD MONROE  
543 W. BAYLESS  
AZUZA, CA 91702

S.C.V. CANYONS PRESERVATION COM.  
MARSHA MCLEAN  
PRESIDENT  
24519 BRECKENRIDGE PL.  
NEWHALL, CA 91321

BS OF A, SAN GABRIEL VALLEY COUNCIL  
JACK BOHLKA  
3450 E. SIERRA MADRE BLVD.  
PASADENA, CA 91107

ED GRANGER  
P.O. BOX 754  
MT. BALDY, CA 91759

MOUNTAIN HIGH RESORT  
MICHELL ROY  
P.O. BOX 3010  
WRIGHTWOOD, CA 92397

VERDUGO PINES BIBLE CAMP  
DON BUTCHER  
P.O. BOX 1989  
WRIGHTWOOD, CA 92397

SHIA  
RONALD MONROE  
543 W. BAYLESS  
AZUSA, CA 91702

P.L.P/SAN GABRIEL PRTY OWNER'S AS.  
GARYLE (DON) ADAMS  
P.O. BOX 1547  
GLENDDORA, CA 91740-1547

ADELPHIA  
JOHN ADAMS  
1041 E. ALOSTA  
GLENDDORA, CA 92886

DON TIDWELL  
4280 VIA ARBOLADA, #306  
LOS ANGELES, CA 90042-5079

THOMAS & PRICE LAW OFFICES  
PAUL R. AYERS, ESQ.  
505 N. BRAND BLVD., 11<sup>TH</sup> FLOOR  
GLENDALE, CA 91203

PUBLIC LAND FOR THE PEOPLE  
CHUCK UCKER  
1453 S. TIMHURST AVE.  
GLENDDORA CA 91740

PATTI LAURSEN  
6017 EUCALYPTUS LANE  
LOS ANGELES, CA 90042

SIERRA CLUB, PASADENA GROUP  
DONALD BREMNER  
1680 WALWORTH AVE.  
PASADENA, CA 91104

FISHERIES RESOURCE VOL CORPS  
BILL REEVES  
6815 NEVADA CT.  
ALTA LOMA, CA 91701



ANTHONY & BARBARA USTICA  
16172 E. MOSSDALE AVE.  
LANCASTER, CA 93535

SIERRA CLUB, CONSERVATION COMMITTEE  
FRANK DOBOS  
602 FRONTENAC AVE.  
LOS ANGELES, CA 90065

WALTER L. WEGNER, JR.  
6544 NEVADA AVE.  
WOODLAND HILLS, CA 91303

DAVID CHIPPING  
1530 BAYVIEW HEIGHTS DR.  
LOS OSOS, CA 93402

ROBERT MCDONALD  
1167 FAIR OAKS, AVE.  
ARROYO GRANDE, CA 93420

HIGH DESERT 4-WHEELERS  
BONNIE FERGUSON  
5711 WEST AVENUE M, SP 41  
QUARTZ HILL, CA 93536

CHESTER CASH  
634 HALCYON DRIVE  
ARROYO GRANDE, CA 93420

FRANK AND RUTH DOBOS  
602 FRONTENAC AVE  
LOS ANGELES, CA 90065

JOHN HOAG  
11866 WILSHIRE BLVD  
LOS ANGELES, CA 90025

SIERRA CLUB, CENTRAL CHAPTER, LA  
GLENN W. ROSEN  
506 N MANSFIELD AVE.  
LOS ANGELES, CA 90036

VULCAN MATERIALS COMPANY  
GARY S DYMESICH  
3200 SAN FERNANDO ROAD  
LOS ANGELES, CA 90065

CAMP MCCLELLAN IMP ASSOCIATION  
ROBERT G VANSCHOONERBERG  
524 DARTMOUTH PLACE  
LA CANADA, CA 91011

CAMP MCCLELLAN IMP ASSOCIATION  
DAVID BLAKESLEE  
89 E. ALEGRIA  
SIERRA MADRE, CA 91024

BONNY SCHUMAKER  
P.O. BOX 583  
LA CANADA, CA 91012-0583

BIG SANTA ANITA CANYON PERMITTEES AS  
FRED VANWICKLE  
550 RAMONA AVENUE  
SIERRA MADRE, CA 91024

JOYLOUISE-HART SMITH  
465 MANZANITA AVE.  
SIERRA MADRE, CA 91024

MILLARD CANYON IMPROVEMENT ASN  
THOMAS HANNA  
515 EL CENTRO STREET  
SOUTH PASADENA, CA 91030

MARY MCGILVRAY  
1510 CHELTEN WAY  
SOUTH PASADENA, CA 91030

MARIANNE LOVE  
1210 N. LOWER AZUSA RD.  
WEST COVINA, CA 91790

SHENG-CHENG KOO  
1325 W. CRUMLEY ST.  
WEST COVINA, CA 91790

PASADENA AUDUBON/SIERRA CLUB  
SYLVIA VIEYRA  
407 N. ELECTRIC # 18  
ALHAMBRA, CA 91801

EARL AND VERAM HANSON  
753 LOMA ALTA TERRACE  
VISTA, CA 92083-3329

BIG SANTA ANITA PERMITTEES ASSOC.  
BARBARA SCHUCK  
723 N BUSHNELL AVE.  
ALHAMBRA, CA 91801

GABRIELINO – TONGVA NATION  
EDWARD BRUNE  
46535 VERDUGO RD.  
BANNING, CA 92220

FREDERIC J. W. KOOLHOF  
3425 DON CARLOS DRIVE  
CARLSBAD, CA 92008

ROBERT MCCLOSKEY  
360 S. ELECTRIC AVE  
MONTEREY PARK, CA 91754

SNOWCREST HEIGHTS IMPROVEMENT ASSOC.  
W.F. MUNDKOWSKY  
PRESIDENT  
P.O. BOX 698  
MT. BALDY, CA 91759

SHIA  
HENRY JUSZCZAK  
9765 KIMBERLY AVENUE  
MONTCLAIR, CA 91763

DANIEL BROLLIAR  
1018 W. SOUTHCLIFF  
SAN DIMAS, CA 91773

MT. BALDY ZEN  
CHRISTOPHER CAIN  
P.O. BOX 429  
MT. BALDY, CA 91759

MICHAEL AND MILDRED LEFFMAN  
430 OAK GLEN COURT  
SAN DIMAS, CA 91773

BRIAN T THORNE  
PO BOX 1431  
WRIGHTWOOD CA 92397-1431

ROBERT WALKER  
P.O. BOX 536  
MT. BALDY, CA 91759

VIRGINIA STEWART  
1725 CALLE CATALINA  
SAN DIMAS, CA 91773

PATRICIA SULLIVAN  
4127 N. MORADA AVENUE  
COVINA, CA 91722

JOHN BENNITT  
PO BOX 1705  
GLEN DORA, CA 91740

RICHARD MARVIN  
727 SCOTTDAL AVE.  
GLENORA, CA 91740

CARRIE MCCARTNEY  
1207 E. CYPRESS  
COVINA, CA 91724

TOM MCKENNA  
PO BOX 694  
GLENORA, CA 91740

NATRC  
GLENDA STEVENS  
21310 E COVINA #46  
COVINA, CA 91724

MARK MATHEWS  
520 E. OCARADAY ST. #21  
GLENORA, CA 91740

KEN & NANCY SUTTON  
811 WICK LN  
GLENORA, CA 91740

DENNIS WELSH  
1315 SODERBERG AVENUE  
GLENORA, CA 91740

SAN GABRIEL CNYN PROPERTY OWNERS AS.  
ROBERTO HERNANDEZ  
4849 ELIZABETH STREET  
BALDWIN PARK, CA 91706

ICE HOUSE CANYON IMP. ASSOC.  
RUTH AND ROBERT BLACK  
1125 IOWA COURT  
CLAREMONT, CA 91711

KLAUS DRAEMER  
P.O. BOX 717  
CHINO HILLS, CA 91709

BARRETT CANYON IMPROVEMENT ASSOC.  
DAVEN GRAY  
860 ALAMOS A ST.  
SAN ANTONIO CANYON TOWN HALL  
CLAREMONT, CA 91711

MICHAEL AND CHRISTY EASTMAN  
4330 LOMBARDAY COURT  
CHINO, CA 91710

GORDON DOUGLASS  
720 MAYFLOWER ROAD  
CLAREMONT, CA 91711

ROBIN IVES  
112 HARVARD, PMB 297  
CLAREMONT, CA 91711

BEATRICE CHURCHILL  
P.O. BOX 216  
CLAREMONT, CA 91711

ALEX TURNER  
160 CASTLETON DRIVE  
CLAREMONT, CA 91711

TERRY GRILL  
1692 CHATTANOOGA CT.  
CLAREMONT, CA 91711

JOHN TRACEY  
4448 OAK LANE  
CLAREMONT, CA 91711

ANNIE MARQUIS  
1038 ALAMOSA  
CLAREMONT, CA 91711

ELAINE HOME  
709 S. BENDER AVE.  
GLENORA, CA 91741

BERNARD & MITZIE SMITH  
PO BOX 2011  
WRIGHTWOOD, CA 92397-2011

DOUGLAS H. MILBURN  
PO BOX 31  
WRIGHTWOOD, CA 92397-0031

PAUL S. CASTLE  
26721 E SWALLOW HILL DR  
WRIGHTWOOD CA 92397

PAT G. & PRUDENCE TURNER  
PO BOX 3281  
WRIGHTWOOD CA 92397-3281

RICHARD W. JOHNSON  
3000 VALENTINE LN  
REDDING, CA 96001

CHRISTOPHER A. ELKIN  
PO BOX 2604  
WRIGHTWOOD, CA 92397-2604

KEVIN M. QUANN  
PO BOX 95  
WRIGHTWOOD, CA 92397-0095

FOX TRUST  
4616 BLACKTHORNE AVE  
LONG BEACH, CA 90808

STEPHEN R MUIR  
PO BOX 36  
WRIGHTWOOD, CA 92397-0036

JEFFREY D & COLLEEN A FLEURY  
PO BOX 204  
ORO GRANDE, CA 92368-0204

JAMES T MACHIN  
PO BOX 1609  
WRIGHTWOOD, CA 92397-1609

JOHN A MARTIN  
15488 CARDLER LN  
VI CA 92392

GARY L & JAYNE E CAMBELL  
3625 LONGVIEW VALLEY RD  
SHERMAN OAKS, CA 91423-4414

REGINALD & JANET CAMPBELL  
26721 E REDSTART STREET  
WRIGHTWOOD, CA 92397

LOUISE MANE  
569 OCCIDENTAL DR  
CLAREMONT, CA 91711

REID D. HANSEN  
PO BOX 1481  
WRIGHTWOOD, CA 92397-1481

REGINALD & JANET CAMPBELL  
450 CODY RD  
SAN DIMAS, CA 91773

HOWARD R. SWITZER  
PO BOX 1628  
WRIGHTWOOD, CA 92397-1628

LOREEN ZAKEM  
PO BOX 3268  
WRIGHTWOOD, CA 92397-3268

FREDERICK C. & SANDRA L. REQUA  
PO BOX 1266  
WRIGHTWOOD, CA 92397-1266

LEON O. & DONNA J. & GARY W. MILLER  
12749 MUROC ST  
NORWALK, CA 90650-4455

STEPHEN J. & ROSALINDA CRAMER  
3167 PAIGE AVE  
SIMI VALLEY, CA 93063

HAZLEWOOD JAMES D & FAMILY TRUST  
PO BOX 2154  
WRIGHTWOOD, CA 92397-2154

REGINALD E. & JANET S. CAMPBELL  
26720 REDSTART DR  
WRIGHTWOOD, CA 92397

GORDON C. & THELMA L. HILL  
PO BOX 2944  
WRIGHTWOOD, CA 92397-2944

BENITO & GINA & FAMILY TRUST  
6078 CANTERBURY DR  
AGOURA HILLS, CA 91301

BRIAN C. THOMPSON  
PO BOX 3175  
WRIGHTWOOD, CA 92397-3175

ALFRIED C. & YVONNE C. BAUER  
PO BOX 133  
WRIGHTWOOD, CA 92397-0133

KENNETH L & DEBRA A MCLAIN  
PO BOX 3360  
WRIGHTWOOD, CA 92397-3360

RICHARD C. OLDENBURG  
PO BOX 149  
WRIGHTWOOD, CA 92397-0149

ROBERT J & PENELOPE A NALL  
PO BOX 3372  
WRIGHTWOOD CA 92397-3372

GARY & KIMBERLY A. WILLIAMS  
615 S CATALINA AVE # 350  
REDONDO BEACH, CA 90277

DANIEL S. & REDONA L. RICE  
PO BOX 2815  
WRIGHTWOOD, CA 92397-2815

EDWARD A. & CINDY K. ZOOK  
PO BOX 2653  
WRIGHTWOOD, CA 92397-2653

KEITH A. & TERESA L. MUNDAY  
PO BOX 1113  
WRIGHTWOOD, CA 92397-1113

ALFREDO P. SIRIGNANO  
DAWSON AVE  
SIGNAL HILL, CA 90806

MARLENE & FAMILY TRUST  
PO BOX 1025  
WRIGHTWOOD, CA 92397-1025

JOHN S & SUSAN C CUNNINGHAM  
17538 BLYTHE STREET  
NORTHRIDGE, CA 91325

DANIEL W. & LINDA M. CAMPHUIS  
PO BOX 902  
WRIGHTWOOD, CA 92397-0902

JOHN S. FOSTER  
PO BOX 1685  
WRIGHTWOOD, CA 92397-1685

CHARLES OLEARY  
23306 N FLUME CANYON DR  
WRIGHTWOOD, CA 92397

THOMAS & MARY HUNTER  
7817 NAYLOR AVE  
LOS ANGELES, CA 90045

MICHAEL F & LINDA L LEE  
PO BOX 1152  
WRIGHTWOOD, CA 92397-1152

DALE M. & DENISE L. JOHNSON  
PO BOX 403  
WRIGHTWOOD, CA 92397-0403

NANCY E ARMSTRONG  
17354 SUNBURST ST  
NORTHRIDGE, CA 91325

MARK J. & VICKI L. WISNIEWSKI  
1734 NOGALES ST  
ROWLAND HGHTS, CA 91748

CRAIG & DIANE TROJANOWSKI  
PO BOX 1550  
WRIGHTWOOD, CA 92397-1550

GARY & JAN M ROSSI  
PO BOX 2358  
WRIGHTWOOD, CA 92397-2358

MALCOLM & MARLENE MEYERS  
PO BOX 1025  
WRIGHTWOOD, CA 92397-1025

RICHARD & MAXINE RANDLE  
8406 SVL BOX  
VICTORVILLE, CA 92392-5125

JAMES W & DOREEN P HOGGAN & TRUST  
PO BOX 950  
WRIGHTWOOD, CA 92397-0950

NANETTE W. ODOM  
26633 TIMBERLINE DR  
WRIGHTWOOD, CA 92397

FIDEL J. NABOR  
2961 MORVALE DR  
THOUSAND OAKS, CA 91361

ROSS  
2210 VISTA PROMESA  
SANTA MARIA, CA 93458

DAVID COLLANDER  
PO BOX 2018  
WRIGHTWOOD, CA 92397-2018

VAHE & MURIEL KHACHONNI  
PO BOX 3056  
WRIGHTWOOD, CA 92397-3056

CHRISTOPHER & KRISTINA ELKIN  
26612 AZUSA & SAN GABRIEL CANYON  
WRIGHTWOOD, CA 92397

RANDAL QUICK  
2571 KEVIN RD  
SAN PABLO, CA 94806-1431

RONALD & KATHLEEN KIRKLAND  
PO BOX 2790  
WRIGHTWOOD, CA 92397-2790

WATSON ELEANOR A & FAMILY TRUST  
1923 COUNTRY CLUB DR  
GLENDDORA, CA 91741

MARK & DOROTHY MCFARLAND  
PO BOX 1268  
WRIGHTWOOD, CA 92397-1268

KAUPER TRUST  
2859 E VANDERHOOF DR  
WEST COVINA, CA 91791

CHARLES W. NELSON  
PO BOX 911  
WRIGHTWOOD, CA 92397-0911

DONALD P & REBECCA M LEWIS  
PO BOX 2924  
WRIGHTWOOD, CA 92397-2924

JOHN J. FITZSIMMONS  
107 VIA TOLUCA  
SAN CLEMENTE, CA 92672

MARK J. & CYNTHIA A. MCCORMICK  
PO BOX 653  
WRIGHTWOOD, CA 92397-0653

DENNIS F. BETHURUM  
27961 VIA DE COSTA  
SAN JUAN CAPO, CA 92675-5376

THOMAS C. SHARP  
23244 CARDINAL RD  
WRIGHTWOOD, CA 92397

MILDRED I BOEHM  
15931 ALTA VISTA DR UNIT C  
LA MIRADA CA 90638

MIKE & MARIA BOKULIC  
PO BOX 2905  
WRIGHTWOOD CA 92397-2905

DONALD H WOOD  
PO BOX 3077  
WRIGHTWOOD CA 92397-3077

ATTENTION: RAY HENSLEY  
ANGELES WATER RESOURCES CONSERVANCY  
STAR ROUTE #1  
LA CANADA, CA 91011

ALICE M ESCALERA TRUST  
P.O. Box 793  
WRIGHTWOOD CA 92397-0793

CARL H & SHANNA L PUELS  
PO BOX 1219  
WRIGHTWOOD CA 92397-1219

JOHN C & PATRICA A GARNER  
PO BOX 2111  
WRIGHTWOOD CA 92397-2111


UNITED METHODIST CHURCH  
1543 BARBARA STREET  
WRIGHTWOOD, CA 92397




## ***Appendix G Project Location Map***

### Figure 1 – Project Location Map

# Project Location Map State Route 39 Brown's Gulch Culvert Rehabilitation





20 0 20 40 Miles



## ***Appendix H Project Area of Impact***

# Brown's Gulch Project Impact Area



## Legend

- Staked Area of Impact
- Trees
- Soilpits
- Streams
- Design Features:**
  - Access Path
  - Culvert Mouth
  - Anticipated Grading
- Image Brown's Gulch Aerial Photo

